



SECOR
INTERNATIONAL
INCORPORATED

www.secor.com
2655 Camino Del Rio North
Suite 302
San Diego, CA 92108
619-296-6195 TEL
619-296-6199 FAX

May 22, 2003

COPY

08OT.04926.00.0013

Mr. Jim Schuck, Project Manager
County of San Diego
Department of Environmental Health
Land and Water Quality Division
P.O. Box 129261
San Diego, CA 92112-9261

RE: REVISED SITE ASSESSMENT AND CLOSURE REPORT
Susan Davey Property
1279/1281 East Main Street
El Cajon, CA 92021
Unauthorized Release #H03126-001

Dear Mr. Schuck:

Pursuant to our telephone conversation on November 13, 2002, enclosed please find a revised version of the original copy of the Site Assessment Report (SAR), dated August 20, 2002, for the subject property. This report was previously provided to you. The additional information contained in the attached report has been prepared by SECOR International Incorporated (SECOR) to amend the SAR for the subject site. The additional information primarily consists of:

- Estimation of the volume of hydrocarbon-impacted soil remaining beneath the site;
- Identification of plans for groundwater utilization at and in the area of the site;
- Description of groundwater conditions in the area of the site; and
- Requested modifications to the Soil Vapor Risk Assessment (Section 5.0).

The amended information is intended to assist you in completing a determination of the eligibility of the subject site for administrative closure. SECOR believes that supplied data presents a strong case for administrative closure.

Mr. Jim Schuck, DEH
Project No. 08OT.04926.00
May 22, 2003
Page 2


If you have any questions regarding the contents of this revised report, please do not hesitate to contact the undersigned at (619) 296-6195.

Respectively Submitted,


SECOR International Incorporated



Jesse A. DeGeorge
Project Manager



Peter J. Rubens
Senior Project Manager



Clifford R. Pollock, CEG #1438
Principal Engineering Geologist

JAD/CRP/PJR/:ch

Enclosures: Revised SAR, dated May 22, 2003



SECOR
INTERNATIONAL
INCORPORATED


www.secor.com
2655 Camino Del Rio North
Suite 302
San Diego, CA 92108
619-296-6195 TEL
619-296-6199 FAX

SITE ASSESSMENT REPORT
REVISION NO. 1
SUSAN DAVEY PROPERTY
1279/1281 East Main Street
El Cajon, California
SECOR Project No. 08OT.04926.00
May 22, 2003


Prepared For
Mr. Richard Reid
Susan Davey Property
7550 Orien Avenue
La Mesa, California 91941

Submitted By
SECOR International Incorporated

Prepared by:


Jesse A. DeGeorge
Project Manager

Reviewed by:



Clifford R. Pollock, CEG #1438
Principal Engineering Geologist



Peter J. Rubens
Senior Project Manager

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1-1
1.1 PURPOSE	1-1
1.2 SCOPE OF SERVICES	1-1
2.0 BACKGROUND INFORMATION	2-1
2.1 SITE DESCRIPTION	2-1
2.2 SITE BACKGROUND	2-1
3.0 REGIONAL GEOLOGIC AND HYDROGEOLOGIC SETTING	3-1
3.1 GEOLOGIC SETTING	3-1
3.2 HYDROGEOLOGIC SETTING	3-1
4.0 OFF-SITE WELL AND SENSITIVE RECEPTOR RESEARCH	4-1
4.1 SENSITIVE RECEPTOR RESEARCH	4-1
4.2 GROUNDWATER UTILIZATION RESEARCH.....	4-1
5.0 SOIL VAPOR RISK ASSESSMENT	5-1
5.1 SOIL VAPOR RISK ASSESSMENT PROCEDURES	5-1
5.2 SOIL VAPOR SAMPLE ANALYTICAL TESTING PROGRAM.....	5-1
5.3 SOIL VAPOR ANALYTICAL RESULTS	5-2
5.4 SOIL VAPOR MIGRATION AND RISK ASSESSMENT	5-2
6.0 SITE ASSESSMENT METHODS	6-1
6.1 PRE-FIELD PREPARATIONS	6-1
6.1.1 Health And Safety Plan	6-1
6.1.2 Drilling Permit.....	6-1
6.1.3 Underground Utility Clearance.....	6-1
6.2 TRENCHING AND SOIL SAMPLING.....	6-1
6.3 DRILLING AND SOIL SAMPLING.....	6-2
6.4 MONITORING WELL PURGING AND SAMPLING.....	6-2
6.5 WASTE MATERIALS MANAGEMENT	6-2
7.0 CHEMICAL TESTING PROGRAM	7-1
7.1 CHEMICAL TESTING PROCEDURES	7-1
7.2 ANALYTICAL RESULTS.....	7-1
7.2.1 Soil Analytical Results--Trenching	7-1
7.2.2 Soil Analytical Results--Drilling	7-1
7.2.3 Groundwater Sampling Analytical Results	7-1
8.0 FINDINGS	8-1
8.1 LOCAL HYDROSTRATIGRAPHIC CONDITIONS	8-1
8.2 GROUNDWATER UTILIZATION	8-1
8.3 SOIL VAPOR SURVEY AND RISK ASSESSMENT	8-1
8.4 SOIL ASSESSMENT	8-2
8.5 GROUNDWATER ASSESSMENT	8-3
9.0 CONCLUSIONS	9-1
10.0 RECOMMENDATIONS	10-1
11.0 LIMITATIONS	11-1
12.0 REFERENCES	12-1

TABLE OF CONTENTS (Cont'd)

TABLES

- Table 1 - Soil Sample Analytical Results--Trenching
- Table 2 - Summary of Soil Sample Analytical Results--Drilling
- Table 3 - Summary of Groundwater Sample Analytical Results
- Table 4 - Summary of Soil Vapor Sample Analytical Results
- Table 5 - Summary of Well Gauging and Elevation Data
- Table 6 - Estimated Volume of TPH-Impacted Soil

FIGURES

- Figure 1 - Site Location Map
- Figure 2 - Site Plan with Cross-Section Lines
- Figure 3 - Site Plan with Former Service Station and Soil Vapor Results (4/19/99 & 1/23/02)
- Figure 4 - Hydrocarbon Concentrations in Soil --Trenching
- Figure 5 - Hydrocarbon Concentrations in Soil -- Drilling
- Figure 6 - Geologic Cross Section A-A'
- Figure 7 - Geologic Cross Section B-B'
- Figure 8 - Geologic Cross Section C-C'
- Figure 9 - Groundwater Elevation Contour Map--for February 19, 2002
- Figure 10 - Hydrocarbon Concentrations in Groundwater--for February 19, 2002
- Figure 11 - Dissolved Benzene Concentration Trends (MW-1)
- Figure 12 - Dissolved Benzene Concentration Trends (MW-2)
- Figure 13 - Dissolved Benzene Concentration Trends (MW-4)

APPENDICES

- APPENDIX A - Soil Vapor Laboratory Report and Chain-of-Custody Documentation
- APPENDIX B - Soil Vapor Risk Calculations and Department of Labor Statistics
- APPENDIX C - Drilling Permit Cover Sheet
- APPENDIX D - Methods and Procedures
- APPENDIX E - Borehole Logs and Legend
- APPENDIX F - Monitoring Well Gauging Log; Well Purging/Sampling Logs
- APPENDIX G - Waste Disposal Documentation
- APPENDIX H - Subsurface Soil and Groundwater Laboratory Reports and Chain-of-Custody Documentation

1.0 INTRODUCTION

PURPOSE

This report presents the results of site assessment activities completed by SECOR International Incorporated (SECOR) at the Susan Davey Property (formerly the Wurzell Estate Property), located at 1279-1281 East Main Street in El Cajon, San Diego County, California (Figure 1). The purpose of this investigation was to evaluate the vertical and areal extent of hydrocarbon-impacted soil and groundwater upgradient and downgradient of, and proximal to, the former underground storage tank (UST) excavation and the former fuel dispenser islands. Field activities were conducted in accordance with SECOR's *Work Plan to Perform Additional Site Assessment*, dated March 12, 2001 (Workplan); and the County of San Diego, Department of Environmental Health, Land and Water Quality Division (LWQD) Workplan approval letter, dated April 3, 2001.

SCOPE OF SERVICES

The following scope of services was performed during the assessment:

- Prepared a site-specific Health and Safety Plan to address potential hazards at the site during assessment activities;
- Obtained a drilling permit from the LWQD for advancement of three soil borings;
- Met with utility representatives to identify and mark locations of subsurface utilities;
- Collected 12 soil vapor samples from six shallow soil boring locations around the Der Wienerschnitzel restaurant building (VP-8 through VP-13; see Figure 2); analyzed all of the samples for benzene, toluene, ethylbenzene and total xylenes (BTEX; see Table 4);
- Supervised the excavation of two trenches (Trench#1 and Trench#2) in the former fuel dispensing area, and the advancement of three soil borings (SB-4 through SB-6);
- Collected 16 soil samples from the trench excavation (seven total) and soil borings (nine total); monitored headspace organic vapors in soil samples with an organic vapor analyzer (OVA) during sampling activities; and analyzed soil samples collected during site assessment activities for total petroleum hydrocarbons as gasoline (TPHg), BTEX and methyl-t-butyl ether (MTBE);
- Purged seven groundwater monitoring wells (MW-1 through MW-7); collected representative groundwater sample from each well; and Analyzed groundwater samples collected from monitoring wells MW-1 through MW-7 for TPHg, BTEX, MTBE, and four other fuel oxygenates, which were t-butyl alcohol (TBA), diisopropyl ether (DIPE), ethyl-t-butyl ether (ETBE), and t-amyl methyl-ether (TAME);
- Used the benzene soil vapor sample analytical results (Table 4; samples collected on 1/22/02) to perform additional health risk modeling to further evaluate potential excess cancer risk to workers in the Der Wienerschnitzel restaurant located on the site;
- Performed a survey to evaluate potential sensitive receptors in the site vicinity; and
- Prepared this report to include a discussion of field procedures, findings, conclusions, and recommendations.

2.0 BACKGROUND INFORMATION

2.1 SITE DESCRIPTION

The subject site is located at the southwest corner of the intersection of East Main Street and Second Street in El Cajon, California. The property is occupied by a Der Wienerschnitzel fast-food restaurant, Los Panchos Restaurant (a Mexican restaurant), an asphalt parking area, and various planters and grass areas (Figure 2).

SITE BACKGROUND

Initial Investigation

During a Phase I Environmental Site Assessment (ESA) conducted by SECOR, records were found that indicated that the site had been operated as a gasoline station from approximately 1960 through 1982 (Figure 3). A review of Polk Directories for the site listed the occupants as Lee's Shell from 1960 to 1969, and Hudson Oil Company from 1970 to 1982. According to LWQD records, four USTs were removed from the site in 1984 and 1985. Based on a sketch found in the files at the City of El Cajon Fire Department, and a 1973 aerial photograph, the USTs were located in the northeast portion of the site. Currently, this area is partially covered by the footprint of the Der Wienerschnitzel building. No information was available on the size or contents of the USTs. According to LWQD records, no soil sampling was conducted during UST removal.

First Subsurface Soil Assessment

In July 1996, soil borings B-1, B-2, and B-3 (see Figure 2) were advanced to depths ranging from 14 to 18 feet below ground surface (bgs). The borings were drilled to evaluate the potential presence of hydrocarbon impacted soil and groundwater from historic releases from the former UST system. Soil samples were collected at approximately 4-foot depth intervals, and grab groundwater samples were collected from each boring to evaluate groundwater quality. TPHg soil concentrations ranged from 410 milligrams per kilogram (mg/kg) in a soil sample from boring B-2 collected at 6.5 feet bgs (sample B2-6.5) to 10,000 mg/kg in sample B2-11; see Figure 5 and Table 2). No TPHg concentrations above laboratory detection limits were reported in the boring B-1 samples collected at 6, 10.5, 15, and 18 feet bgs; and in three samples collected below the water table in borings B-2 and B-3 (at sample depths ranging from 14 to 18 feet bgs). Benzene concentrations ranged from nondetectable (<0.05 mg/kg) in seven samples to 29 mg/kg in sample B2-11. A total recoverable petroleum hydrocarbon (TRPH) concentration of 6,400 mg/kg was reported for sample B3-11. TPHg concentrations in the grab groundwater samples ranged from 40,000 to 120,000 micrograms per liter (µg/L). Similarly, benzene concentrations in the three grab groundwater samples ranged from 89 to 10,000 µg/L (see Table 3).

The preliminary analytical results were forwarded to the LWQD, which opened an unauthorized release case for the site. Based on the soil and groundwater petroleum hydrocarbon constituent concentrations and the location of the site within a beneficial groundwater use area, the LWQD directed that a site assessment be performed to evaluate the extent of hydrocarbon impact to soil and groundwater.

First Groundwater Conditions Assessment

In March 1998, a SECOR geologist supervised the drilling and sampling of four shallow well borings (MW-1 through MW-4, see Figure 2). Each well boring was completed as a groundwater monitoring well. No TPHg concentrations above the laboratory reportable limit (10 mg/kg) were reported in the soil samples collected from well borings MW-1 through MW-3. One of the three soil samples from well boring MW-4 (the 10-foot depth sample) contained 2,851 mg/kg TPHg with 16 mg/kg benzene (see Figure 5 and Table 2). Following development, each of the newly installed monitoring wells was sampled. The representative groundwater samples from all four wells contained detectable concentrations of TPHg and BTEX constituents. Well MW-2 contained the highest concentrations of each analyzed constituent. The MW-2 groundwater sample contained 174,000 µg/L, with respective BTEX analyte concentrations of 3,940; 3,620; 1,500; and 4,310 µg/L. MTBE was detected only in the MW-1 groundwater sample (at 17.6 µg/L). None of the samples contained detectable soluble lead concentrations above 100 µg/L (see Table 3).

The results of the groundwater characterization assessment were presented to the LWQD in a report, titled *Site Assessment Report*, dated April 28, 1998. The LWQD reviewed the report and requested additional site assessment. Better determination of the lateral extent of hydrocarbon impacted groundwater was required, as well as an evaluation of the potential cancer risk to employees of the existing on-site businesses.

First Soil Vapor Survey Collection and Health Risk Assessment

On April 19, 1999, a SECOR geologist supervised the advancement of seven shallow soil vapor probes (VP-1 through VP-7; see Figure 2). Soil vapor samples were collected from each newly-installed vapor probe. Vapor samples collected from the four vapor probes located adjacent to the Der Wienerschnitzel restaurant building (VP-1 through VP-4) contained benzene concentrations ranging from nondetectable (less than 0.1 micrograms per liter of vapor; µg/L-vapor) to 1,079 µg/L-vapor at 2 feet bgs and from 2.8 µg/L-vapor to 750 µg/L-vapor at 5 feet bgs. By contrast, soil vapor samples collected from the three vapor probes advanced adjacent to the Los Panchos restaurant building (VP-5 through VP-7) contained nondetectable benzene vapor concentrations at both depths (2 and 5 feet bgs). The soil vapor sample analytical results are presented on Table 4. The average of the benzene analytical results were used in the SAM Vapor Risk Assessment Model. Based on the results of the model, SECOR concluded that the increased cancer risk to workers in the two on-site restaurants due to residual benzene vapor concentrations beneath the site presents less than a one in a million increased cancer risk.

Second Groundwater Conditions Assessment

On May 31 and June 7, 2000, a SECOR geologist supervised the drilling and sampling of three additional well borings (MW-5 through MW-7; see Figure 2). Each well boring was completed as a shallow groundwater monitoring well. No TPHg, benzene or MTBE concentrations above the laboratory reporting limits were found in the soil samples from well borings MW-5 through MW-7. The laboratory reporting limits were 0.5 to 10 mg/kg for TPHg, 0.005 mg/kg for BTEX constituents, and 0.005 mg/kg for MTBE (see Figure 5 and Table 2). Following development, each of the existing or newly installed monitoring wells was purged and sampled. The groundwater samples from wells MW-1, MW-2 and MW-4 contained detectable concentrations of TPHg and BTEX constituents; those in the sample from well MW-2 were the highest. The MW-2 groundwater sample was found to contain 7,900 µg/L TPHg, with respective BTEX concentrations of 1,100; 340; 420; and 1,000 µg/L. No TPHg or BTEX constituent

concentrations above the respective laboratory reporting limits (0.5 to 50 ug/L) were found in the groundwater samples from wells MW-3 and MW-5 through MW-7. Similarly, no MTBE concentrations were detected in the groundwater samples from wells MW-2, MW-3, and MW-5 through MW-7. MTBE concentrations of 52 and 1.2 µg/L were reported for wells MW-1 and MW-4, respectively (see Figure 5 and Table 2).

Subsurface Utility Survey

In June 2000, SECOR personnel conducted a subsurface utility survey. As part of the work scope, SECOR reviewed available subsurface utility maps prepared by San Diego Gas and Electric (SDG&E) (for gas and electric lines), Pacific Bell (for telephone lines), Helix Water District (for water supply lines), and the City of El Cajon (for sanitary sewer lines). The results of the map search were ground-truthed. The purpose of the investigation was to identify potential man-made contaminant migration pathways in the vicinity of the subject property. Several utility lines were determined to be present, at depths ranging from approximately 3 to 5 feet bgs, in the site vicinity. Utility line research also indicated the presence of sewer lines located in the site vicinity. Since the burial depths of these sewer lines were unknown, SECOR concluded that the lines potentially could provide a hydrocarbon migration pathway (see Figure 2).

Current Site Investigation

The results of SECOR's May 2000 groundwater conditions investigation and June 2000 subsurface utility survey were presented to the LWQD in a document, titled *Site Assessment Report* (SAR), dated August 22, 2000. Following review of the SAR, the LWQD requested that additional site assessment work be performed at the site. Specifically, the LWQD directed that a better determination of the lateral and vertical extent of hydrocarbon-impacted soil in the vicinity of the former UST system be performed. Although not required by the LWQD, SECOR decided to also re-evaluate the potential excess cancer risk to workers at the Der Wienerschnitzel fast-food restaurant based on the analytical results for soil vapor samples VP2-2 and VP2-5 (Table 4); and to perform a survey of potential sensitive receptors in the site vicinity.

The results of this additional site assessment are included in succeeding sections of this report. Section 4.0 presents the results of the off-site well and sensitive receptor surveys. Section 5.0 presents additional benzene soil vapor health risk assessment modeling results in the area of the Der Wienerschnitzel restaurant building. Intrusive site investigation results are presented in Section 6.0. Details of the analytical testing program are provided in Section 7.0. A summary of the findings of this phase of the investigation are presented in Section 8.0. Conclusions regarding the spatial extent (both lateral and vertical) of hydrocarbon-impacted subsurface soils and groundwater and a recommendation for a no further action required determination based on those conclusions are presented in Section 10.0.

3.0 REGIONAL GEOLOGIC AND HYDROGEOLOGIC SETTING

3.1 GEOLOGIC SETTING

According to Kennedy (1975), the El Cajon area consists of Holocene-age alluvial sediments, underlain by pre-Tertiary-age granitic rocks of the Southern California Batholith. Drilling and soil sampling activities performed by SECOR personnel indicate that the subject site is underlain by artificial fill overlying Quaternary-age alluvium. Observations made during drilling activities suggest that the site lithology, to a depth of at least 20 feet bgs, generally consists of sands, clayey sands, silty sands, and silts.

Subsurface soil consists of clayey and silty sands, poorly graded sands with clays, and silts with sand from surface to approximately 12 feet bgs, the maximum depth of exploration for this investigation. The soils are identified as artificial fill overlying Quaternary-age alluvium. These results are consistent with the deeper well borings that have been advanced on the site for installation of groundwater monitoring wells MW-1 through MW-7.

3.2 HYDROGEOLOGIC SETTING

According to the California Regional Water Quality Control Board, San Diego Region (RWQCB), the subject site is located in the El Cajon Hydrologic Subarea (HSA 7.13) of the Lower San Diego Hydrologic Area (HA 7.10) of the San Diego Hydrologic Unit (HU 7.00). Groundwater in the El Cajon HSA has been designated as beneficial use for municipal and agricultural supply, and potentially beneficial use for industrial service and process water supply. Depth to first encounter of groundwater beneath the subject site varies seasonally from approximately 8 to 11 feet bgs. Groundwater in the shallow aquifer is under unconfined conditions. Therefore, the water table represents the surface of the uppermost aquifer. Groundwater flow direction is toward the northwest at a gradient ranging from 0.009 vertical feet per horizontal foot (ft/ft).

4.0 OFF-SITE WELL AND SENSITIVE RECEPTOR RESEARCH AND GROUNDWATER UTILIZATION RESEARCH

4.1 SENSITIVE RECEPTOR RESEARCH

SECOR performed an off-site sensitive receptor survey to evaluate potential adverse impacts of the dissolved gasoline plume on surrounding sensitive receptors. For the purpose of this evaluation, the sensitive receptors researched were domestic or production water supply wells, surface water bodies, schools and day care centers. As part of the evaluation, SECOR performed the following activities: 1) reviewed agency water well databases; 2) reviewed the EcoSearch™ and GeoTracker™ databases; 3) reviewed the U.S.G.S. El Cajon, California 7.5-minute quadrangle topographic map; and 4) performed a windshield survey of properties located within a 550-foot radius of the site vicinity. SECOR also contacted personnel from the Helix Water District (HWD) for information on sources of potable water for the site vicinity.

4.2 GROUNDWATER UTILIZATION RESEARCH

Subject site database research, five water wells were identified within a one half-mile radius of the subject site. All of the wells were located hydrologically cross-gradient (with respect to the groundwater flow direction) to the site. All of these wells were listed as "destroyed" on the database reviewed at the Department of Environmental Health. None of the identified wells were located within a 500-foot radius of the subject site. SECOR personnel then conducted a field receptor survey (windshield survey) to confirm the existence or absence of the wells identified in the agency database research. None of the listed wells were found within the 500-foot site radius. Moreover, no surface water bodies, schools or day care facilities were located within a one-half mile radius of the site.

In November 2002, Mr. Joe Young, a Water Systems engineer with the HWD, was contacted by SECOR regarding any plans that HWD might have to install future water supply wells in the vicinity of the Susan Davey Property site. Mr. Young indicated that the HWD currently has no water supply wells, and that there are no plans for HWD to install wells in their service area. This service area includes the vicinity of the intersection of Main Street, East Main Street and Jamacha Road.

Nearby Former Bob's Automotive Site Groundwater Utilization Research

During the late 1990's, SECOR performed site assessment activities at a nearby site (Former Bob's Automotive) also located in the El Cajon HSA with similar hydrogeologic conditions. The Former Bob's Automotive site is located at 1492 East Main Street approximately 4,500 feet to the northeast of the Susan Davey Property site. As part of the assessment activities at the Former Bob's Automotive site, a comprehensive analysis of actual groundwater conditions in the El Cajon HSA, including groundwater quality assessment and an aquifer pumping test, was conducted.

According to the results of the aquifer pumping test at the Former Bob's Automotive site, the uppermost water-bearing zone in the El Cajon HSA can yield more than 200 gallons per day from 4-inch diameter extraction wells. Analytical testing of selected groundwater samples from well MW-2 at the Former Bob's Automotive site contained elevated concentrations of chloride, nitrates as nitrogen ($\text{NO}_3\text{-N}$), total dissolved solids (TDS), and exhibited high electrical conductivity (EC) values. The chloride, nitrates, and TDS concentrations all exceeded their respective State drinking water maximum concentration limits (MCLs; SECOR, 1998). According to HWD guidelines, these four parameters (e.g., chloride, $\text{NO}_3\text{-N}$, TDS, and EC) are

the main indicators of groundwater quality, and hence of groundwater usability for potable purposes. Therefore, based on SECOR's field observations, laboratory analytical results, and information obtained from regulatory agencies and from state and local water district authorities, there appears to be a very low probability that shallow groundwater in the vicinity of either the Former Bob's Automotive or nearby Susan Davey Property sites in the El Cajon HSA will ever be used, especially for municipal water supply.

During its groundwater conditions evaluation in the area of the former Bob's Automotive Site, SECOR interviewed several knowledgeable HWD personnel, including Mr. Bob Friegden and Ms. Debra Hack. Mr. Friegden was the HWD General Manager and District Engineer. Ms. Hack was HWD's public educator. According to Mr. Friegden, no groundwater well could be pumped (in the HWD service area) for potable water supply without first pre-treating it at the wellhead to remove biological and other contaminants from the groundwater prior to its distribution. Such wellhead treatment was determined by the HWD to be prohibitively expensive. Mr. Friegden indicated that the HWD was aware of the elevated concentrations of chloride, $\text{NO}_3\text{-N}$, TDS, and EC values in shallow groundwater in their service area. A potential future water supplier other than the HWD or private parties would incur significant costs when performing State-mandated monthly monitoring to confirm that the water did not exceed State MCLs. Mr. Friegden concluded that it would be much less expensive to buy water from the HWD than to treat groundwater at the well head to meet the MCLs. Furthermore, Mr. Friegden confirmed that the City of El Cajon receives all of its water from the HWD (SECOR, 1998). According to Debra Hack, the HWD historically operated up to 12 water supply wells within the El Monte Basin in the past. However, Ms. Hack further stated that the HWD has never had any water supply wells in the El Cajon HSA (or basin as she referred to it, since the HWD does not utilize the terms used by the RWQCB). Since the time that imported surface water from the Colorado River Basin became available, the HWD has reduced its production from the El Monte Basin well field to approximately 250 acre-feet per year. Currently, 90 percent of HWD's water comes from the Colorado River Basin, and the remaining 10 percent is from surface runoff to Lake Cuyamaca and to El Capitan Reservoir. According to Ms. Hack, the HWD has never pumped water from the El Cajon HSA and has no plans to do so (SECOR, 1998).

5.0 SOIL VAPOR RISK ASSESSMENT

SECOR performed additional potential human health risk assessment modeling to further evaluate the excess cancer risk posed by subsurface benzene vapors to workers at the Der Wienerschnitzel fast-food restaurant located on-site. The additional risk assessment modeling was performed using benzene vapor concentrations obtained from the current soil vapor sample analyses. The purpose of the additional risk assessment was to further demonstrate that the benzene remaining beneath the Der Wienerschnitzel fast-food restaurant presents less than a one in a million increased cancer risk to workers.

5.1 SOIL VAPOR RISK ASSESSMENT PROCEDURES

On January 22, 2002, SECOR personnel conducted an additional soil vapor survey at the site. The survey included installation and sampling of six soil vapor probes (VP-8 through VP-13; see Figure 3) around the perimeter of the Der Wienerschnitzel fast-food restaurant building. The sampling locations were selected to evaluate the presence of volatile organic compounds (VOCs) in soil vapor beneath the building. The sampling locations were selected to assess areas that had not been covered during the April 1999 soil vapor survey and to re-assess the area around VP-2 (SECOR, 2000). Vapor samples were collected from each probe at approximate depths of 2 and 5 feet bgs.

HP Labs (HP) of Solana Beach, California performed the soil vapor survey. HP (1998) describes the typical sampling procedures used to collect and analyze soil vapor samples at similar sites. The sampling apparatus consists of polyethylene tubing within a 1.5-inch nominal diameter push rod (drive tube), connected to a syringe within a hardened-steel drop-off point. The vapor sampling point is threaded onto the leading edge of a 1.5-inch nominal diameter probe rod and advanced to the desired sampling depth using a Strataprobe® hydraulic direct-push drilling system. Once inserted to the desired depth, the probe rod is retracted approximately one to two inches, thereby exposing the vapor sampling port to the subsurface soil. Approximately three dead volumes of air then are extracted through the syringe to flush the sample probe and tubing prior collecting the sample. Upon completion of vapor purging, the soil vapor samples are collected using a 30-cubic centimeter (cc) vacuum syringe. Each 30-cc syringe is transported to a mobile laboratory on-site for immediate analysis. Each direct-push boring then is backfilled with hydrated granular bentonite and capped with either cold-patch asphalt or cement paste to match the original surface.

HP performed the vapor survey at the site in accordance with the above-described procedures. Downhole pushing and sampling equipment were either changed out (i.e., the disposable vapor sampling points) or thoroughly decontaminated between uses (i.e., undamaged drive tubes). Drive tubes that were bent or otherwise rendered unserviceable were decontaminated and discarded. Decontamination consisted of scrubbing in a tri-sodium phosphate detergent solution, rinsing in a tap water bath, and final rinsing in a deionized water bath.

5.2 SOIL VAPOR SAMPLE ANALYTICAL TESTING PROGRAM

Twelve soil vapor samples were submitted for analysis to an on-site HP mobile laboratory. HP is a state-certified laboratory based in Escondido, California. The soil vapor samples were analyzed for BTEX constituents by U.S. EPA Method 8260B.

5.3 SOIL VAPOR SAMPLE ANALYTICAL RESULTS

Soil vapor sample analytical results, including locations and sample depths, are summarized in Table 4 and on Figure 3. A copy of the HP laboratory report is provided in Appendix A.

Benzene vapor concentrations ranged from 4.1 to 75 µg/L-vapor in the four samples with detectable concentrations. Benzene vapor was not detected in the other eight samples at a concentration greater than the laboratory detection limit, or equipment quantitation limit (EQL) of 1 µg/L-vapor. The EQL for toluene, ethylbenzene, and total xylenes was also 1 µg/L-vapor. Toluene vapor concentrations ranged from 1.3 to 4.1 µg/L-vapor in seven of the samples; ethylbenzene vapor concentrations ranged from 1.2 to 3.9 µg/L-vapor in three samples; and total xylenes vapor concentrations ranged from 1.6 to 4.5 µg/L-vapor in the three samples in which it was detected.

As would be expected, the highest BTEX vapor concentrations were found in the 5-foot sample from vapor probe VP-10 (sample VP10-5) for benzene, ethylbenzene and total xylenes; and the 5-foot sample from VP11 (sample VP11-5) for toluene. As shown on Figure 3, sample VP10-5 was collected near the northeast corner of the Der Wienerschnitzel building; and sample VP11-5 was taken at the northwest corner of a grassy area to the northwest of the building. Soil vapor probe VP10 is located adjacent to former UST excavation, and probe VP11 is located down-gradient of the former UST excavation. Also, both of these probes and respective samples are located in the vicinity of VP-2.

5.4 SOIL VAPOR MIGRATION AND RISK ASSESSMENT

SECOR used the benzene soil vapor sample analytical data in Table 4 for the Current Assessment Activities – 1/22/02 to estimate the potential excess cancer risk to humans resulting from diffusion of benzene vapor (the selected target compound) from hydrocarbon-impacted soil and groundwater, through the vadose zone and into the Der Wienerschnitzel restaurant building built on a typical slab-on-grade foundation. The benzene vapor concentrations in the most shallow (2-foot bgs) samples were averaged to derive a single value for running the SAM Vapor Risk Model. Where actual analytical concentrations were less than the laboratory detection limit, the detection limit of 1 µg/L-vapor was used to calculate the average benzene soil vapor concentration.

In accordance with the current and foreseeable future use of the site, conservative SAM commercial/industrial worker exposure criteria were used. The soil vapor migration and risk assessment calculations were performed using the SAM Vapor Risk Assessment Model (Version: November 1999; Revised: January 8, 2002). The calculations were completed using SAM default, site-specific, and updated parameters including those indicated below:

- Slab Attenuation Factor = 0.1 (SAM conservative default for an exiting slab);
- Ventilation Rate = 0.83 air exchanges per hour (commercial/industrial default)
- Room Height = 8 feet (2.44 meters; SAM conservative default);
- Total Soil Porosity = 0.3 (SAM conservative default);
- Soil Air Porosity = 0.2 (SAM conservative default);

- Soil Gas concentration (Measured) = 5.17 µg/L-vapor benzene (site specific, average of soil vapor sample concentrations at 2 feet; 0.61 meter bgs);
- Depth of Contamination or Soil Gas = 2 feet (0.61 meter);
- Exposure duration = 7 years (U.S. Department of Labor, bureau of Labor Statistics; to be conservative, 7 years is approximately 2.7 times the median Service Industry workers, that includes restaurant workers tenure of 2.6 years for 1983-2002; see Appendix B for references); and
- Hours Per Day = 12 hours (SAM conservative industrial/commercial worker default).

Based on these parameters the benzene total indoor air concentration (C_i) estimated by the SAM Vapor Risk Model is 6.93E-04 (or 6.93×10^{-4}) µg/L-vapor.

Potential excess cancer risk calculations using the benzene C_i estimate were performed using equations from the U.S. Environmental Protection Agency (EPA) Risk Assessment Guidance (RAG) for Superfund Sites (EPA, 1989) contained in the SAM Vapor Risk Assessment Model. The calculations were completed using the conservative SAM default parameters in the model including those indicated below:

- Slope Factor = 0.1 milligrams per kilograms-day (mg/kg-day)⁻¹;
- Inhalation Rate = 20 cubic meters per day (m^3/day);
- Body Weight = 70 kilograms;
- Averaging Time = 25,550 days (70 years); and
- Reference Dose = 0.0017 mg/kg-day.

The potential excess cancer risk to humans from benzene vapor at 2 feet bgs for workers in the Der Wienerschnitzel restaurant building was calculated to be 6.78E-07 (or 6.78×10^{-7}), equating to an excess cancer probability of 1 in 1,474,926. This result indicates that the benzene vapor beneath the Der Wienerschnitzel fast-food restaurant building does not pose a significant threat to human health. A copy of the printouts of the SAM Vapor Risk Assessment Model spreadsheets for the Susan Davey Property - Der Wienerschnitzel Restaurant Building are presented in Appendix B.

The conservative health risk calculations indicate that, under current subsurface conditions and commercial/industrial exposure criteria, benzene vapor migration into the Der Wienerschnitzel fast-food restaurant building should not pose a threat to human health of workers above a one-in-a-million risk level. The most conservative concentrations and risk scenarios indicate that the increased potential cancer risk is less than the SAM acceptable cancer risk.

6.0 SITE ASSESSMENT METHODS

This section presents a description of the field methods and procedures that were used to conduct intrusive investigations of subsurface soil and groundwater conditions at the site.

6.1 PRE-FIELD PREPARATION

6.1.1 Health And Safety Plan

A site-specific Health and Safety Plan was prepared by SECOR prior to initiation of field activities. On-site personnel were required to review the Health and Safety Plan prior to commencement of the site assessment and were instructed to conduct field activities in accordance with plan guidelines.

6.1.2 Drilling Permit

Prior to commencing assessment activities, SECOR submitted a permit application and appropriate fees to the LWQD for the installation of three soil borings. The LWQD approved the permit request on December 10, 2001. A copy of the approved drilling permit is provided in Appendix C.

6.1.3 Underground Utility Clearance

Prior to drilling activities, potential drilling locations were marked on-site and Underground Service Alert (USA) was notified. USA notified local utility companies of the scheduled subsurface investigation, and representatives of the affected utilities marked their underground utilities. In addition, SECOR met with Subsurface Alert, Inc., a private utility locator, to mark on-site underground utilities.

6.2 TRENCHING AND SOIL SAMPLING

In an attempt to determine if abandoned product piping was left in the subsurface of the subject site, SECOR excavated a shallow exploratory trench adjacent to the former location of the fuel dispenser islands. On February 7, 2002, a SECOR geologist supervised the excavation of subsurface soil in this area. Trench 1 was 53-feet in length and approximately 3-feet deep. Similarly, Trench 2 was 58-feet in length and the same depth. Qual-Pac Services performed the excavation work. During the excavation activities, SECOR did not observe any evidence of abandoned product piping or petroleum hydrocarbon impact including stained soil or fuel odors. SECOR used an organic vapor analyzer (OVA) to segregate the soil removed from the trenches during the excavation activities. The OVA registered readings of 0 parts per million volumetric (ppmv) for all of the soil that was removed. The soil excavated from the exploratory trenches was stockpiled on-site. Following the excavation activities, SECOR collected seven soil samples (SS-1 through SS-7) from the floors of the trenches (Figure 4). A portion of each of the stockpiled soil samples was screened for the presence of organic vapors using the OVA. Based on field evidence (including visual observation, olfactory cues and no measurable OVA readings) and the soil sample analytical results (which indicated that no petroleum hydrocarbons were present in the stockpiled soil samples above method detection limits), the excavated soil was re-used to backfill the trenches.

6.3 DRILLING AND SOIL SAMPLING

On March 5, 2002, a SECOR geologist supervised the drilling and sampling of three soil borings (SB-4, SB-5 and SB-6; see Figure 2 and Figure 5). The borings were drilled by Tri-County Drilling (TCD) using a CME 75 drilling rig equipped with 8-inch outside diameter, continuous-flight, hollow-stem augers (HSAs).

During drilling, soil samples were collected at depths of 5, 10 and 12 feet bgs in each boring. The samples were collected, prepared, and screened for the presence of organic vapors using the procedures presented in Appendix D. A SECOR geologist logged the soil cuttings using the visual/manual method for the Unified Soil Classification System (USCS), as prescribed in ASTM Standard D 2488-93. Edited boring logs are provided in Appendix E. Downhole drilling and sampling equipment was decontaminated in accordance with the decontamination procedures described in Appendix D. Soil cuttings generated during drilling activities were placed in 55-gallon drums, labeled, centrally located, and left on-site pending receipt of the results of laboratory analyses and determination of appropriate waste disposal.

6.4 MONITORING WELL PURGING AND SAMPLING

On February 19, 2002, depth to static water (DTW) was measured in wells MW-1 through MW-7 using an electronic water level meter. Following gauging, the wells were purged using disposable Teflon bailers and sampled in accordance with LWQD guidelines (provided in the 2002 SAM Manual). Based on LWQD guidelines, wells MW-1 and MW-3 through MW-7 were characterized as fast recharging; approximately 1.5 borehole volumes of water were removed from each well to allow fresh formational water to enter. Well MW-2 was characterized as slow recharging; approximately one borehole volume of water was removed from this well prior to sampling. Three water-quality indicators (i.e., electrical conductivity, pH, and temperature) were measured repeatedly during purging to assist in evaluating when a sufficient volume of stagnant water had been removed.

Groundwater samples were collected from each well in clean disposable bailers and transferred to acidified 40-ml glass vials. The water samples were delivered to a California-certified analytical laboratory (ZymaX Envirotechnology of San Luis Obispo, California) for chemical analysis. Monitoring well sampling and decontamination procedures are described in Appendix D. DTW and well purging and sampling data were recorded on Monitoring Well Gauging Logs and on Well Purging/Sampling Logs. A copy of these logs is provided in Appendix F. Purged water was placed in two 55-gallon steel drums, labeled, centrally-located, and left on-site pending receipt of laboratory results and determination of appropriate waste disposal.

6.5 WASTE MATERIALS MANAGEMENT

As noted in the preceding sections, soil cuttings and purged groundwater were stored on-site in labeled 55-gallon steel drums. Soil cuttings were waste profiled using the sample analytical results from the soil borings. Drummed wastewater was categorized on the basis of the groundwater analytical results from the well sampling event. The wastes were handled as follows:

- Soil cuttings were transported by EFR Environmental Services, Inc. (EFR) as non-hazardous materials to Dome Rock Industries, Inc for treatment and/or disposal.
- Drummed purge water was transported by EFR as non-hazardous waste to Dome Rock Industries, Inc for treatment and/or disposal.

EFR transported the drummed wastes on March 20, 2002 under a non-hazardous waste manifest. A copy of the waste manifest is provided in Appendix G.

7.0 CHEMICAL TESTING PROGRAM

7.1 CHEMICAL TESTING PROCEDURES

Select soil samples collected during the drilling activities were analyzed by ZymaX Envirotechnology, Inc. (ZymaX) for TPHg, BTEX, and MTBE using EPA Method 8260 and GC/MS combination (equivalent to EPA Method 8260B). In addition, the trench soil samples were analyzed by HP for TPHg using CA DHS Method, and for BTEX and MTBE using EPA Method 8260B. Groundwater samples from the monitoring wells were analyzed by ZymaX for the following analytes: TPHg, BTEX, MTBE, TAME, TBA, DIPE and ETBE by EPA Method 8260 and GC/MS combination. This method is equivalent to EPA Method 8260B.

7.2 ANALYTICAL RESULTS

7.2.1 Soil Analytical Results--Trenching

Analytical results are summarized in Table 1; and TPHg, benzene and MTBE concentration distributions are illustrated on Figure 4. A copy of the laboratory report and chain-of-custody documentation is included in Appendix H. No TPHg, BTEX or MTBE concentrations above the respective constituent laboratory detection limits were reported in the seven soil samples (SS-1 through SS-7) collected from the bottom of Trench 1 and Trench 2.

7.2.2 Soil Analytical Results--Drilling

Analytical results are summarized in Table 2; and TPHg and benzene concentration distributions are illustrated on Figure 5. A copy of the laboratory report and chain-of-custody documentation is included in Appendix H.

TPHg concentrations were reported above the laboratory detection limit (<0.5 mg/kg) in four of the nine samples submitted for analysis. Detectable concentrations of TPHg ranged from 80 mg/kg in sample SB-4/10' to 1,800 mg/kg in sample SB-5/12'. The remaining five samples contained nondetectable TPHg concentrations.

Benzene concentrations were reported above the laboratory detection limits (ranging from <0.005 to 0.1 mg/kg) in four of the nine samples submitted for analysis. Detectable benzene concentrations ranged from 0.015 mg/kg in sample SB-6/10' to 3.9 mg/kg in sample SB-5/12'. The remaining five soil samples contained non-detectable benzene concentrations. Similarly, detectable concentrations of toluene, ethylbenzene and total xylenes were found in the same four samples. The maximum concentrations were 44 mg/kg toluene, 22 mg/kg ethylbenzene and 150 mg/kg total xylenes. All of these were found in the 12-foot sample from boring SB-5 (sample SB-5/12'). This boring was located in the north-central portion of the Susan Davey Property between the Los Panchos Restaurant and the Der Wienerschnitzel building. No MTBE concentrations above laboratory detection limits (<0.005 to 0.5 mg/kg) were reported in any of the soil samples submitted for analysis.

7.2.3 Groundwater Sampling Analytical Results

Laboratory analytical results are summarized in Table 3; and the dissolved TPHg, benzene and MTBE concentrations are illustrated on Figure 10. A copy of the laboratory report and chain-of-custody documentation is included in Appendix H.

TPHg concentrations were reported above the laboratory detection limit (<50 µg/L) in three of the seven samples submitted for analysis. Detectable concentrations of TPHg ranged from 480 µg/L in the sample from well MW-4 to 6,300 µg/L in the sample from well MW-2. The remaining four groundwater samples contained non-detectable concentrations of TPHg. Similarly, the groundwater samples from the same three wells (MW-1, MW-2 and MW-4) contained detectable concentrations of BTEX analytes. The most heavily impacted well is well MW-2, which contained 640 µg/L benzene, 83 µg/L toluene, 270 µg/L ethylbenzene and 830 µg/L total xylenes. The lowest detectable BTEX concentrations were 39 µg/L benzene, 0.6 µg/L toluene, 19 µg/L ethylbenzene and 0.9 µg/L total xylenes. With the exception of ethylbenzene (which was collected from well MW-4), all of these values were found in the sample from well MW-1. As shown on Figure 2, well MW-1 is located to the northwest of the Der Wienerschnitzel building (close to vapor point VP11), and well MW-4 is located near the southwest corner of the Los Panchos Restaurant. Well MW-2 is located near the northeastern corner of the Los Panchos Restaurant.

MTBE concentrations were reported above the laboratory detection limit (ranging from <0.5 to <20 µg/L) in two of the seven well water samples (samples MW-1 and MW-4). Sample MW-1 contained 78 µg/L MTBE, and sample MW-4 contained 0.7 µg/L MTBE. In addition, all of the groundwater samples were analyzed for four other fuel oxygenates (TBA, DIPE, ETBE and TAME). A TBA concentration (10 µg/L) was found in only sample (from well MW-1). Detectable DIPE concentrations ranged from 0.9 µg/L in sample MW-4 to 680 µg/L in sample MW-2. DIPE concentrations were not detected in four of the samples (samples MW-3 and MW-5 through MW-7). No ETBE or TAME concentrations were reported above their respective laboratory detection limits (which ranged from <0.5 to <20 µg/L) in any of the seven well water samples.

8.0 FINDINGS

Based on the results of the additional site assessment activities described above in Sections 3.0 through 7.0, SECOR presents the following findings on site conditions and the impacts of hydrocarbon-impacted soil and groundwater on sensitive receptors in the site vicinity.

8.1 LOCAL HYDROSTRATIGRAPHIC CONDITIONS

Subsurface soil consists of clayey and silty sands, poorly graded sands with clays, and silts with sand from surface to approximately 12 feet bgs, the maximum depth of exploration for this investigation. The soils are identified as artificial fill overlying Quaternary-age alluvium. These results are consistent with the deeper well borings that have been advanced on the site for installation of groundwater monitoring wells MW-1 through MW-7.

No groundwater was encountered during drilling to 12 feet bgs in various portions of the site. However, the reported static water level depths in existing monitoring wells ranged from 8.66 to 10.92 feet bgs. This suggests that groundwater locally is under semi-confined (instead of water table) conditions, since the apparent piezometric rise in the wells is at least 1.08 to 3.34 feet. SECOR calculated the groundwater flow direction to be to the northwest at a gradient of 0.009 ft/ft (Figure 9), using the surveyed well locations, surveyed wellhead elevations from Table 5, and the February 19, 2002 DTW measurements. Depictions of lithologic and hydrostratigraphic relationships in subsurface soils across the site are shown in Figure 6, Figure 7 and Figure 8.

8.2 GROUNDWATER UTILIZATION

Five water wells were identified on various agency databases as being located within a one-half-mile radius of the site. However, none of these wells are still in service. No surface water bodies, schools or day care facilities are located within the same one-half mile radius of the site.

The groundwater quality assessment, and current and planned utilization information collected by SECOR for the Susan Davey Property site and nearby Former Bob's Automotive site indicate that the HWD does not consider the groundwater beneath the subject site (located in the El Cajon Basin) to be a feasible source of potable water. According to knowledgeable HWD individuals, it is unlikely that groundwater in the site vicinity would ever be used by HWD as a municipal potable source due to the costs associated with wellhead treatment and with State-mandated MCL compliance monitoring. Groundwater sample analytical results and HWD officials indicate that the uppermost water-bearing zone in the El Cajon Basin contains elevated concentrations of chloride, $\text{NO}_3\text{-N}$, TDS, and EC values. All of these parameters exceed their respective State drinking water MCLs (SECOR, 1998). Consequently, the groundwater is considered by the HWD to be non-potable.

Additionally, even if the groundwater beneath the Susan Davey Property site were potable, the subsurface utility lines identified to be present in its immediate vicinity most likely would preclude the installation of a water supply well. It should also be noted that certain subsurface utility lines such as sewer lines and storm drains have the potential to cause unwanted cross-contamination of water supply wells.

8.3 SOIL VAPOR SURVEY AND RISK ASSESSMENT

The results of the additional soil vapor survey presented in this report confirm that detectable BTEX soil vapor concentrations are present in the subsurface of the site. None of the detected BTEX vapor concentrations pose a threat to the health of workers in the Der Wienerschnitzel

fast-food restaurant and Los Panchos Restaurant. Specifically, there is less than a one-in-a-million increased cancer risk for workers in the restaurants who potentially would inhale benzene vapors.

8.4 SOIL ASSESSMENT

Elevated concentrations of TPHg and benzene were found in the 12-foot samples from soil borings SB-4 (located to the north of the Der Wienerschnitzel building) and SB-5 (located midway between the two restaurant buildings in the north central portion of the site). Soil samples from these two borings also contained detectable concentrations of toluene, ethylbenzene and total xylenes; the maximum concentrations of each constituent were found in the 12-foot sample from boring SB-5 (sample SB-5/12').

Soil sample analytical data indicate that soil containing total petroleum hydrocarbons as gasoline (TPHg) concentrations above 100 milligrams per kilogram (mg/kg) is present in the vicinity of the former underground storage tank (UST) excavation and former fuel dispenser islands. Specifically, the impact to soil appears to be present in the vicinity of the release sources and has migrated to the soil/water ("capillary fringe") zone. At this location (i.e., capillary fringe zone), the impact appears to have remained. TPHg concentrations exceeding 100 mg/kg (including a maximum of 10,000 mg/kg in sample B2-11) were reported in soil samples collected from soil borings B2, B3, SB-4, SB-5 and MW-4 at depths ranging from approximately 6.5 to 12.5 feet below ground surface (bgs; a 6-foot thick hydrocarbon impacted soil zone). Also, it should be noted that in certain areas within the plume the hydrocarbon impacted soil zone lessens in thickness to approximately 9.5 to 12.5 feet bgs (a 3-foot thick hydrocarbon impacted soil zone). TPHg concentrations were less than 100 mg/kg in 27 of 35 soil samples collected and analyzed from this area during this and previous phases of site investigation work.

Based on the distribution of soil samples indicating TPHg-impacted soil containing less than 100 mg/kg, the vertical extent of TPHg in soil with concentrations exceeding 100 mg/kg conservatively was estimated to be from 6.5 to 12.5 feet bgs to 9.5 to 12.5 feet bgs (6-foot to 3-foot thick zone of impact) in the vicinity of the former UST excavation and fuel dispensers. The zone of impact was approximated further by assuming that the thickness dividing line of the soil zone of impact (i.e., 6-foot to 3-foot) is approximately 20 feet west of SB-5. Due to the irregular shape of the assessed zone of TPHg-impacted soil and to simplify the TPHg mass calculations, the area of TPHg-impacted soil conservatively was estimated to be rectangular-shaped. This rectangular-shaped plume has a dimension of approximately 90 feet wide by 160 feet long by 6 to 3 feet thick. The determination was based on hydrocarbon concentrations and estimates of the vertical and lateral extent of hydrocarbon-impacted soil.

Based on the conservatively estimated rectangular plume area, soil sample TPHg concentrations, and an average soil plume thickness of 6 to 3 feet, SECOR estimates that the volume of impacted soil with TPHg concentrations greater than 100 mg/kg is approximately 2,743 in-place cubic yards. Most of these soil samples appear to have concentrations greater than 1,000 mg/kg. The mass of TPHg in soil is estimated to be 18,253 pounds or 2,795 gallons of gasoline (Table 6). The mass estimate was calculated by multiplying the average TPHg concentrations of the soil within the 100 mg/kg concentration plume area (i.e., 2,241 mg/kg) by the estimated volume of TPHg impacted material by the density of the materials (estimated at 3,000 pounds per cubic yard). Pounds of TPHg were converted to gallons by assuming that one-gallon of fuel weighs 6.53 pounds. Refer to Figures 5, 6, 7, and 8 for depictions of the estimated volume of hydrocarbon-impacted soils remaining in place beneath the site.

8.5 GROUNDWATER ASSESSMENT

Groundwater in the shallow aquifer beneath the site has been impacted by motor fuel hydrocarbons, including TPHg, BTEX constituents, MTBE, TBA and DIPE. The horizontal limit of dissolved hydrocarbon impact to groundwater at the site (in all directions) is defined by perimeter wells MW-3, MW-5, MW-6 and MW-7. Samples collected from these wells have not contained dissolved TPHg, benzene or MTBE concentrations above laboratory detection limits. Hydrocarbon-impacted groundwater appears to be limited to the vicinity of wells MW-1 (located near the Der Wienerschnitzel building), MW-2 (located between the two restaurant buildings, but closer to Los Panchos Restaurant) and MW-4 (located near the western wall of the Los Panchos Restaurant), all of which are either located in the center of and/or immediately cross-gradient from the former UST excavation and dispenser islands (Figures 9 and 10).

Groundwater samples collected from the four site perimeter wells have contained either low or non-detectable concentrations of dissolved gasoline petroleum hydrocarbons for the last four years. Therefore, based on the groundwater analytical data collected to date, the dissolved hydrocarbon plume appears to be stable and to be limited in horizontal extent to the vicinity of wells MW-1, MW-2 and MW-4. Figures 11, 12 and 13 depict graphs illustrating dissolved benzene decreasing concentration trends in MW-1, MW-2 and MW-4 (the three wells located in the significantly impacted portion of the site). Although an increase in benzene concentrations were observed in MW-1 (1.6 ug/L to 39 ug/L), the increase is not considered to be significant.

Additionally, low to non-detectable dissolved MTBE concentrations have been reported in groundwater samples collected from two of the six groundwater monitoring wells during the past four years. Dissolved MTBE concentrations in groundwater samples collected from MW-1 have ranged from 17.6 µg/L (sample collected on April 1, 1998) to 78 µg/L (sample collected in mid-February 2002). Based on these analytical data, MTBE is not a constituent of concern at the site. SECOR believes that MTBE beneath the site (albeit, low levels), originated from the gasoline previously used at the subject site.

Since the dissolved hydrocarbon plume (i.e., benzene) is associated directly with remaining hydrocarbon impact to capillary fringe soil at the subject site, it is not possible to precisely predict the number of years will be necessary for dissolved benzene to degrade naturally (by aerobic biodegradation) to its MCL. Based on the decreasing dissolved benzene concentration trend over the last five years of groundwater data, age and stability of the plume, dissolved benzene concentrations would be expected to degrade to its MCL in several decades to 100 years or more. As discussed in Section 4.0, the HWD has no plans for utilizing the groundwater beneath the subject site for potable uses in the present and in the foreseeable future. Therefore, it is reasonable to assume that the groundwater in the subject site vicinity will not be considered as a potable water source within the above-mentioned degradation timeframe by the HWD.

9.0 CONCLUSIONS

Based on the information presented in this report, and summarized from other reports, SECOR concludes that a "No Further Action Required" determination is appropriate for the Susan Davey Property site. The following bulleted items describe the pertinent information and conclusions made for consideration of closure of the case for the subject site:

- The subject site gasoline service station has not operated since 1982. In 1985, four known USTs were removed from the site. Moreover, recent shallow exploratory trenching in the vicinity of the former fuel dispenser islands has demonstrated that there is no evidence of product piping or additional USTs at the subject site. Therefore, SECOR concludes that there is no current ongoing UST-related contaminant release sources associated with the Susan Davey Property site.
- Although groundwater in the area of the subject site (El Cajon HSA) is designated by the RWQCB as having beneficial uses for municipal and agricultural water supply, no current or planned future uses of groundwater resources in the vicinity of the subject site are known to exist. Furthermore, economic considerations related to the prohibitive costs for wellhead treatment needed to reduce TDS, nitrates, and other existing undesirable groundwater constituents, along with expensive and long-term State-mandated MCL compliance monitoring requirements, make the use of the groundwater by the HWD or other parties undesirable at the present time and in the foreseeable future.
- The gasoline release to soil at the subject site has been characterized adequately. SECOR estimates that the volume of impacted soil with TPHg concentrations greater than 100 mg/kg is approximately 2,743 in-place cubic yards. The mass of TPHg in soil is estimated to be 18,253 pounds or 2,795 gallons of gasoline. The groundwater sample analytical results for the February 19, 2002, sampling event indicate that the extent of residual groundwater impact has been defined adequately. The plume of groundwater contamination is stable, dissolved concentrations have been observed to be on a decreasing trend and no further site investigation and/or mitigation is required.
- No sensitive receptors are threatened by the gasoline released at the site. Specifically, no groundwater production wells are located within one-half mile radius from the Susan Davey Property site.
- Based on the results of two soil vapor surveys and human health risk assessments, SECOR concludes that the gasoline released at the site, specifically the carcinogen benzene, presents no significant risk to the health of the workers in the Los Panchos and Der Wienerschnitzel restaurants on the subject site.
- Since the dissolved hydrocarbon plume (i.e., benzene) is associated directly with remaining hydrocarbon impact to capillary fringe soil at the subject site, it is not possible to precisely predict the number of years that will be necessary for dissolved benzene to degrade naturally to its MCL. Based on the decreasing dissolved benzene concentration trend observed in the five years of groundwater sample analytical data collected at the site, the plume's age and stability, dissolved benzene concentrations would be expected to degrade to its MCL in several decades to 100 years or more. The HWD has no plans for utilizing the groundwater beneath the subject site for potable uses in the near or foreseeable future. Therefore it is reasonable to assume that the groundwater in the subject site vicinity will not be considered as a potable water source by the HWD within the plume degradation timeframe.

10.0 RECOMMENDATIONS

Based on the conclusions presented in Section 9.0 of this report, SECOR recommends that the hydrocarbons present in the soil and groundwater at the subject site be allowed to attenuate naturally. No additional environmental or human health risk assessment or active remediation is recommended. As demonstrated by the data collected to date, the Susan Davey Property site presents no adverse risks to human health or to the beneficial uses of surface or groundwater resources. SECOR recommends that a "No Further Action Required" determination be assigned to the case associated with the Susan Davey Property site.

11.0 LIMITATIONS

The findings and conclusions contained in this report have been prepared for the specific application to this project and have been developed in a manner consistent with that level of care and skill normally exercised by members of the environmental scientific profession currently practicing under similar conditions in the area at the time this investigation was performed. No warranty, either expressed or implied, is made. This report is for the exclusive use of Susan Davey and her representatives.

A potential always remains for the presence of the unknown, unidentified, or unforeseen subsurface contamination. Further evidence against such potential site contamination would require additional subsurface exploration and testing.

12.0 REFERENCES

Technical References

California Code of Regulations (CCR), 1998, Identification and Listing of Hazardous Waste, Criteria for Identifying the Characteristics of Hazardous Waste, Characteristic of Toxicity, Title 22, Chapter 11, Article 2, Section 66261.24.

CCR, 1998, Domestic Water Quality and Monitoring Regulations, Primary Standards - Inorganic Chemicals, Maximum Contaminant Levels-Inorganic Chemicals, Title 22, Chapter 15, Article 4, Section 64431.

CCR, 2000, Domestic Water Quality and Monitoring Regulations, Primary Standards, Organic Chemicals, Maximum Contaminant Levels-Organic Compounds, Title 22, Chapter 15, Article 5.5, Section 64444.

California Regional Water Quality Control Board, San Diego Region (RWQCB), 1994, Comprehensive Water Quality Control Plan, San Diego Basin (9).

County of San Diego, Site Assessment and Mitigation Program (SAM), 2003, Site Assessment and Mitigation Manual.

Kennedy, M.P. and G.L. Peterson, 1975. Geology of the San Diego Metropolitan Area, California, California Division of Mines and Geology Bulletin 200, Sacramento, California.

U.S. Geological Survey (USGS), 1967. 7.5-Minute Series Quadrangle Topographical Map, El Cajon Quadrangle, California. Scale 1" = 2,000'. Photorevised in 1975.

Consultant LWQD, and U.S. Department of Labor References

County of San Diego Department of Environmental Health, Land and Water Quality Division (LWQD) Work Plan Approval Letter, dated April 13, 2001.

SECOR International Inc., 1996. Limited Site Assessment Report, Susan Davey Property, 1279/1281 East Main Street, El Cajon, California. SECOR, San Diego, California. August 28.

SECOR International Inc., 1998. Site Assessment Report, Susan Davey Property, 1279/1281 East Main Street, El Cajon, California. SECOR, San Diego, California. April 28.

SECOR, 1998, Groundwater Quality and Aquifer Evaluation, Soil Gas Survey and On-and Off-Site Assessment Report, Former Bob's Automotive, 1492 East Main Street, El Cajon, California, dated June.

SECOR International Inc., 2000. Site Assessment Report, Susan Davey Property, 1279/1281 East Main Street, El Cajon, California. SECOR, San Diego, California. August 22.

SECOR International Inc., 2001. Work Plan to Perform Additional Site Assessment, Susan Davey Property, 1279/1281 East Main Street, El Cajon, California. SECOR, San Diego, California. March 12, 2001.

U.S. Department of Labor, Bureau of Labor Statistics, 2002, Employee Tenure Summary 1983-2002, Contact: Mr. Randy Ilg (202-691-6378) also see Appendix B of this report.

TABLES

TABLE 1
SOIL SAMPLE ANALYTICAL RESULTS - TRENCHING
 Susan Davey Property
 All concentrations reported in milligrams per kilograms (mg/kg).

Sample ID	Sample Depth (ft. bgs)	Date Sampled	TPHg	B	T	E	X	MTBE
SS-1	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01
SS-2	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01
SS-3	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01
SS-4	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01
SS-5	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01
SS-6	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01
SS-7	3	02/07/02	<10	<0.01	<0.01	<0.01	<0.02	<0.01

Notes:

- TPHg = Total petroleum hydrocarbons as gasoline (C₆-C₁₂)
- B = Benzene
- T = Toluene
- E = Ethylbenzene
- X = Total xylenes
- MTBE = Methyl-t-butyl ether
- TRPH = Total recoverable petroleum hydrocarbons
- bgs = Below ground surface
- = Not analyzed
- <# = Below laboratory detection limit

TABLE 2
SUMMARY OF SOIL SAMPLE ANALYTICAL RESULTS - DRILLING
 Susan Davey Property
 All concentrations reported in milligrams per kilogram (mg/kg).

Sample ID	Sample Depth (bgs)	Date Sampled	TPHg	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	TPRH
Previous Assessment Activities - 7/2/96-6/7/00													
B1-6	6	7/2/1996	<10	<0.05	<0.05	<0.05	<0.15	--	--	--	--	--	--
B1-10.5	10.5	7/2/1996	<10	0.007	<0.005	0.008	0.044	--	--	--	--	--	--
B1-15	15	7/2/1996	<10	<0.05	<0.05	<0.05	<0.15	--	--	--	--	--	--
B1-18	18	7/2/1996	<10	<0.05	<0.05	<0.05	<0.15	--	--	--	--	--	--
B2-6.5	6.5	7/2/1996	410	0.18	<0.5	<0.5	<0.15	--	--	--	--	--	--
B2-11	11	7/2/1996	10,000	29	270	120	800	--	--	--	--	--	--
B2-14.5	14.5	7/2/1996	<10	<0.05	<0.05	<0.05	<0.15	--	--	--	--	--	--
B3-6.5	6.5	7/2/1996	2,100	<5	<5	11	15	--	--	--	--	--	--
B3-11	11	7/2/1996	2,800	<0.5	<0.5	26	68	--	--	--	--	--	6,400
B3-15	15	7/2/1996	<10	<0.05	<0.05	<0.05	<0.15	--	--	--	--	--	--
B3-18	18	7/2/1996	<10	<0.05	<0.05	<0.05	<0.15	--	--	--	--	--	--
MW-1/5	5	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-1/10	10	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-2/5	5	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-2/10	10	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-3/5	5	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-3/10	10	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-4/5	5	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-4/10	10	3/25/1998	2,851	16.0	148	50.6	349.0	--	--	--	--	--	--
MW-4/15	15	3/25/1998	<10	<0.05	<0.05	<0.05	<0.05	--	--	--	--	--	--
MW-5/15	15	5/31/2000	<0.5	<0.005	<0.005	<0.005	<0.005	<0.005	<0.05	<0.005	<0.005	<0.005	--
MW-5/20	20	5/31/2000	<0.5	<0.005	<0.005	<0.005	<0.005	<0.005	<0.05	<0.005	<0.005	<0.005	--
MW-6/15	15	5/31/2000	<0.5	<0.005	<0.005	<0.005	<0.005	<0.005	<0.05	<0.005	<0.005	<0.005	--
MW-6/20	20	5/31/2000	<0.5	<0.005	<0.005	<0.005	<0.005	<0.005	<0.05	<0.005	<0.005	<0.005	--
MW-7/15	15	6/7/2000	<0.5	<0.005	<0.005	<0.005	<0.005	<0.005	<0.05	<0.005	<0.005	<0.005	--
MW-7-20	20	6/7/2000	<0.5	<0.005	<0.005	<0.005	<0.005	<0.005	<0.05	<0.005	<0.005	<0.005	--

TABLE 2
SUMMARY OF SOIL SAMPLE ANALYTICAL RESULTS - DRILLING
 Susan Davey Property
 All concentrations reported in milligrams per kilogram (mg/kg).

Sample ID	Sample Depth (bgs)	Date Sampled	TPHg	B	T	E	X	TAME	TBA	DIPE	ETBE	MTBE	TPRH
Current Assessment Activities-03/05/02													
SB-4/5'	5	03/05/02	<0.5	<0.005	<0.005	<0.005	<0.005	--	--	--	--	<0.005	--
SB-4/10'	10	03/05/02	80	<0.1	<0.1	0.4	1.2	--	--	--	--	<0.1	--
SB-4/12'	12	03/05/02	1,400	0.9	21	20	190	--	--	--	--	<0.5	--
SB-5/5'	5	03/05/02	<0.5	<0.005	<0.005	<0.005	<0.005	--	--	--	--	<0.005	--
SB-5/10'	10	03/05/02	960	1.5	18	11	69	--	--	--	--	<0.5	--
SB-5/12'	12	03/05/02	1,800	3.9	44	22	150	--	--	--	--	<0.5	--
SB-6/5'	5	03/05/02	<0.5	<0.005	<0.005	<0.005	0.015	--	--	--	--	<0.005	--
SB-6/10'	10	03/05/02	<0.5	0.015	0.04	0.007	0.028	--	--	--	--	<0.005	--
SB-6/12'	12	03/05/02	<0.5	<0.005	<0.005	<0.005	<0.005	--	--	--	--	<0.005	--

Notes: TPHg = Total petroleum hydrocarbons as gasoline

B = Benzene

T = Toluene

E = Ethylbenzene

X = Total xylenes

TAME = t-amyl methyl ether

TBA = t-butyl alcohol

DIPE = Diisopropyl ether

ETBE = Ethyl-t-butyl ether

MTBE = Methyl-t-butyl ether

TPRH = Total recoverable petroleum hydrocarbons

bgs = Below ground surface

-- = Not analyzed

<# = Below method reporting limit

TABLE 3
SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
 Susan Davey Property
 All concentrations reported in micrograms per liter (µg/L)

Sample ID	Date Sampled	TPHg	B	T	E	X	MTBE	TBA	DIPE	ETBE	TAME	Total Lead
B1-W	07/02/96	40,000	2,200	76	990	320	NA	NA	NA	NA	NA	NA
B2-W	07/02/96	120,000	10,000	19,000	2,600	20,000	NA	NA	NA	NA	NA	NA
B3-W	07/02/96	56,000	89	49	170	530	NA	NA	NA	NA	NA	NA
MW-1	04/01/98	260	8.9	<2.5	18.4	<5.0	17.6	NA	NA	NA	NA	NA
	05/26/99	150	<0.5	<0.5	0.7	<5.0	48	NA	NA	NA	NA	NA
	06/12/00	150	1.9	<0.5	2.2	<0.5	52	NA	NA	NA	NA	NA
	09/12/00	<500	<2	<2	<2	<6	57	<10	92	<2	<2	NA
	12/12/00	170	1.6	<0.5	5.1	<0.5	54	<0.5	81	<0.5	<0.5	NA
	02/19/02	700	39	0.6	69	0.9	78	10	46	<0.5	<0.5	NA
MW-2	04/01/98	174,000	3,940	3,620	1,500	4,310	<400	NA	NA	NA	NA	NA
	05/26/99	12,000	1,400	980	710	2,200	<20	NA	NA	NA	NA	NA
	06/12/00	7,900	1,100	340	420	1,000	<10	NA	NA	NA	NA	NA
	09/12/00	15,000	2,200	730	990	2,300	<100	<500	730	<100	<100	NA
	12/12/00	8,200	1,100	170	480	910	<50	<500	1,000	<50	<50	NA
	02/19/02	6,300	640	83	270	830	<20	<200	680	<20	<20	NA
MW-3	04/01/98	166	0.9	<0.5	<3.0	2	<0.5	NA	NA	NA	NA	NA
	05/26/99	<50	<0.5	<0.5	<0.5	<0.5	<0.5	NA	NA	NA	NA	NA
	06/12/00	NS	NS	NS	NS	NS	NS	NA	NA	NA	NA	NA
	07/31/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	NA	NA	NA	NA	NA
	09/12/00	<500	<2	<2	<2	<6	<2	<10	<2	<2	<2	NA
	12/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<50	<0.5	NA	NA
	02/19/02	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA
MW-4	04/01/98	9,790	810	613	145	884	<25	NA	NA	NA	NA	<0.1
	05/26/99	1,600	290	160	85	280	<2.0	NA	NA	NA	NA	NA
	06/12/00	600	130	69	34	100	1.2	NA	NA	NA	NA	NA
	09/12/00	<500	12	7.3	4.1	14	<2	<10	<2	<2	<2	NA
	12/12/00	93	17	3	3.6	12	0.8	<5.0	0.6	<0.5	<0.5	NA
	02/19/02	480	59	11	19	54	0.7	<5.0	0.9	<0.5	<0.5	NA

TABLE 3
SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
 Susan Davey Property
 All concentrations reported in micrograms per liter (µg/L)

Sample ID	Date Sampled	TPHg	B	T	E	X	MTBE	TBA	DIPE	ETBE	TAME	Total Lead
MW-5	06/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	NA	NA	NA	NA	NA
	12/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA
	02/19/02	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA
MW-6	06/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	NA	NA	NA	NA	NA
	09/12/00	<500	<2	<2	<2	<6	<2	<10	<2	<2	<2	NA
	12/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA
MW-7	02/19/02	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA
	06/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	NA	NA	NA	NA	NA
	09/12/00	<500	<2	<2	<2	<6	<2	<10	<2	<2	<2	NA
	12/12/00	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA
	02/19/02	<50	<0.5	<0.5	<0.5	<0.5	<0.5	<5.0	<0.5	<0.5	<0.5	NA

Notes: TPHg = Total petroleum hydrocarbons as gasoline
 B = Benzene
 T = Toluene
 E = Ethylbenzene
 X = Total xylenes
 TAME = tert-amyl methyl ether
 TBA = tert-butyl alcohol
 DIPE = Diisopropyl ether
 ETBE = Ethyl tert-butyl ether
 MTBE = Methyl-t-butyl ether
 <# = Below laboratory detection limit
 NS = Not sampled
 Shaded row represents the most recent groundwater sampling event.

TABLE 4
SUMMARY OF SOIL VAPOR SAMPLE ANALYTICAL RESULTS

Susan Davey Property

All concentrations reported in micrograms per liter of vapor (µg/L-vapor)

All samples analyzed by EPA Method 8260B

Sample Identification	Date Collected	Sample Depth (Ft bgs)	Benzene	Toluene	Ethylbenzene	Total Xylenes
Previous Assessment Activities - 04/19/99 - Der Wienerschnitzel Restaurant Building Area						
VP1-2	4/19/1999	2	<0.1	<0.1	<0.1	<0.1
VP1-5	4/19/1999	5	4.2	0.9	<0.1	<0.1
VP2-2	4/19/1999	2	1,079	545	31	99
VP2-5	4/19/1999	5	750	102	27	96
VP3-2	4/19/1999	2	0.39	<0.1	<0.1	<0.1
VP3-5	4/19/1999	5	54	18	<0.1	<0.1
VP4-2	4/19/1999	2	3.2	8.3	1.5	4.0
VP4-5	4/19/1999	5	2.8	7.3	1.7	2.5
Previous Assessment Activities - 04/19/99 - Los Panchos Restaurant Building Area						
VP5-2	4/19/1999	2	<0.1	<0.1	<0.1	<0.1
VP5-5	4/19/1999	5	<0.1	<0.1	<0.1	<0.1
VP6-2	4/19/1999	2	<0.1	<0.1	<0.1	<0.1
VP6-5	4/19/1999	5	<0.1	<0.1	<0.1	<0.1
VP7-2	4/19/1999	2	<0.1	<0.1	<0.1	<0.1
VP7-5	4/19/1999	5	<0.1	<0.1	<0.1	<0.1
Current Assessment Activities - 1/22/02 - Der Wienerschnitzel Restaurant Building Area						
VP8-2	01/22/02	2	<1	<1	<1	1.8
VP8-5	01/22/02	5	<1	<1	<1	<1
VP9-2	01/22/02	2	<1	<1	<1	<1
VP9-5	01/22/02	5	<1	<1	<1	<1
VP10-2	01/22/02	2	18	<1	1.7	1.9
VP10-5	01/22/02	5	75	1.3	3.9	2.1
VP11-2	01/22/02	2	9	1.4	<1	1.6
VP11-5	01/22/02	5	4.1	4.1	1.2	4.6
VP12-2	01/22/02	2	<1	2.4	<1	2.5
VP12-5	01/22/02	5	<1	2.2	<1	2.1
VP13-2	01/22/02	2	<1	2.3	<1	2.1
VP13-5	01/22/02	5	<1	1.8	<1	1.9

Notes: VP8-2 = Vapor point sampling location identification - depth
Ft bgs = Feet below ground surface
= micrograms per liter

TABLE 5
SUMMARY OF WELL GAUGING AND ELEVATION DATA
Susan Davey Property

Well No.	Date	SWE	DTW (feet bgs)	LPH Thickness (feet)	GWE (feet)
MW-1	04/01/98	479.42	7.75	0	471.67
	05/26/99	479.42	9.32	0	470.10
	06/12/00	479.42	9.50	0	469.92
	09/12/00	479.42	9.75	0	469.67
	12/12/00	479.42	9.84	0	469.58
	02/19/02	479.42	9.80	0	469.62
MW-2	04/01/98	480.00	8.77	0	471.23
	05/26/99	480.00	10.36	0	469.64
	06/12/00	480.00	10.55	0	469.45
	09/12/00	480.00	10.83	0	469.17
	12/12/00	480.00	10.99	0	469.01
	02/19/02	480.00	10.92	0	469.08
MW-3	04/01/98	478.35	6.76	0	471.59
	05/26/99	478.35	8.16	0	470.19
	06/12/00	478.35	NM	0	NC
	09/12/00	478.35	8.61	0	469.74
	12/12/00	478.35	9.93	0	468.67
	02/19/02	478.35	8.70	0	469.65
MW-4	04/01/98	478.60	7.66	0	470.94
	05/26/99	478.60	9.30	0	469.30
	06/12/00	478.60	9.49	0	469.11
	09/12/00	478.60	9.80	0	468.80
	12/12/00	478.60	9.93	0	468.67
	02/19/02	478.60	9.88	0	468.72
MW-5	06/12/00	478.71	10.37	0	468.34
	02/19/02	478.71	10.81	0	467.90
MW-6	06/12/00	478.93	8.30	0	470.63
	09/12/00	478.93	8.56	0	470.37
	12/12/00	478.93	8.69	0	470.24
	02/19/02	478.93	8.66	0	470.27
MW-7	06/12/00	479.04	10.25	0	468.79
	09/12/00	479.04	10.57	0	468.47
	12/12/00	479.04	10.72	0	468.32
	02/19/02	479.04	10.70	0	468.34

Notes: GWE = Groundwater elevation, in feet above mean sea level (AMSL)
 SWE = Surveyed well elevation, in feet AMSL, surveyed relative to a City of El Cajon benchmark.
 DTW = Depth to water, in feet below top of well casing
 LPH = Liquid-phase hydrocarbons
Shaded row represents most recent groundwater sampling event.

TABLE 6

ESTIMATED VOLUME OF TPH-IMPACTED SOIL

Susan Davey Property

Area of Concern	Volume Of Soil With TPH Concentrations Exceeding 100 mg/kg (1)				Mass of TPH in Soil with TPH Concentrations Exceeding 100 mg/kg (2)		
	Area (ft ²)	Thickness (ft)	Volume (ft ³) (yd ³)		Mean (mg/kg)	Mass (lbs)	Gallons
<i>Estimated Volume</i>							
Soil in the vicinity of the former UST Excavation and Fuel Dispensers (West of SB-5)	9,442	3	28,326	1,049	2,241	6,983	1,069
Soil in the vicinity of the former UST Excavation and Fuel Dispensers (East of SB-5)	7,620	6	45,720	1,693	2,241	11,270	1,726
TOTALS	17,062	-	74,046	2,742	-	18,253	2,795

Total estimated volume of impacted soil
with TPH concentrations exceeding 100 mg/kg:

2,742 yd³


Total mass of TPH in soil with
TPH concentrations exceeding 100 mg/kg:

18,253 lbs. or 2,795 gallons

Notes:

- (1) Includes soil within the projected 100 milligrams per kilogram (mg/kg) TPH limits delineated in Figures 5, 6, 7 and 8. Estimated volume calculations were made on the basis of approximate volume of the maximum assessed extent of TPH-impacted soil with concentrations exceeding 100mg/kg, and on the basis of the geometric mean concentrations calculated from soil sample analytical results.
- (2) The mass calculations were made by multiplying the calculated soil volume by the geometric mean TPH concentration by the density of the soil (3,000 pounds per cubic yard assumed). When soil sample data was not available for a particular volume of soil, the geometric mean from the nearest volume of soil was used for mass calculations. Gallons of gasoline calculated by assuming one gallon of gasoline 6.53 pounds.

FIGURES



0 1320 2640
APPROXIMATE SCALE IN FEET

SECOR

International Incorporated

2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

k:\Allprojects\2001\dwgs\General\Daveyprop\Daveyloc.dwg

PROJECT: 008.04711

DATE: 1/31/01


NOTES:

FIGURE 1

SITE LOCATION MAP

SUSAN DAVEY PROPERTY

1279 & 1281 E. MAIN STREET
EL CAJON, CALIFORNIA




SECOR

INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

SITE PLAN WITH CROSS-SECTION LINES
SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CA.

PROJECT No.:
080T.04926.00

FIGURE: 2



NOTE: FORMER BUILDING, DISPENSER ISLANDS AND UST LOCATIONS ARE APPROXIMATE BASED ON A 1973 AERIAL PHOTOGRAPH

0 50 100
APPROXIMATE SCALE IN FEET

SECOR


INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

SITE PLAN WITH FORMER SERVICE STATION AND SOIL VAPOR RESULTS (4/19/99 AND 1/23/02)

SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CA.

PROJECT No.:
080T.04926.00

FIGURE: 3



LEGEND:

ALLEY

- SOIL SAMPLE LOCATIONS
- SOIL BORING
- ⊕ GROUNDWATER MONITORING WELL
- × VAPOR PROBES (SECOR 4/19/99, AND 1/23/02)
- TPHg TOTAL PETROLEUM HYDROCARBONS AS GASOLINE
- MTBE METHYL-TERT-BUTYL ETHER
- BGS BELOW GROUND SURFACE


3 | <10 | <0.01 | <0.01
 SOIL SAMPLE DEPTH IN FEET BGS/TPHg/BENZENE/MTBE
 CONCENTRATIONS IN MILLIGRAMS PER KILOGRAM (mg/kg)

UST UNDERGROUND STORAGE TANK

--- PROPERTY LINE

▭ TRENCH

NOTE: FORMER BUILDING, DISPENSER ISLANDS AND UST LOCATIONS
 ARE APPROXIMATE BASED ON A 1973 AERIAL PHOTOGRAPH



SECOR

INTERNATIONAL INCORPORATED
 2655 CAMINO DEL RIO N., SUITE 302
 SAN DIEGO, CA. 92108


DAVEYHCT.DWG

5/14/02

HYDROCARBON CONCENTRATIONS
 IN SOIL - TRENCHING
 SUSAN DAVEY PROPERTY
 1279 & 1281 E. MAIN STREET
 EL CAJON, CA.

PROJECT No.:
 08OT.04926.00

FIGURE: 4



LEGEND:

- SOIL BORING
- ⊕ GROUNDWATER MONITORING WELL
- × VAPOR PROBES (SECOR 4/19/99, AND 1/23/02)


TPHg TOTAL PETROLEUM HYDROCARBONS AS GASOLINE
BGS BELOW GROUND SURFACE

6.5 2,100 <5

SOIL SAMPLE DEPTH IN FEET BGS/TPHg/BENZENE
CONCENTRATIONS IN MILLIGRAMS PER KILOGRAM (mg/kg)



PERIMETER OF FORMER UST AND DISPENSER ISLAND
EXCAVATION



0 50 100
APPROXIMATE SCALE IN FEET

SECOR

INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

DAVEYHC.DWG

6/1/03


**HYDROCARBON CONCENTRATIONS
IN SOIL - DRILLING**

SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CA.

PROJECT No.:


080T.04926.00

FIGURE: 5



LEGEND:

- SOIL SAMPLE LOCATION
- (2,851) TOTAL PETROLEUM HYDROCARBONS AS GASOLINE (TPHg), CONCENTRATIONS IN MILLIGRAMS PER KILOGRAM (mg/kg)
- ▽ STATIC GROUNDWATER LEVEL
- ND NOT DETECTED
- MONITORING WELL
- BLANK
- SCREENED INTERVAL
- TPHg CONCENTRATIONS >100 mg/kg IN SOIL
- SM SILTY SAND
- SC CLAYEY SAND
- SP POORLY GRADED SAND
- SP/SC POORLY GRADED SAND WITH CLAY



SECOR
INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

GEOLOGIC CROSS SECTION A-A'


SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CALIFORNIA

CAD FILE NO.: X-SECAA

PROJECT No.:
080T.04926.00


DATE: 4/26/02

FIGURE: 6



LEGEND:

- SOIL SAMPLE LOCATION
- (410) TOTAL PETROLEUM HYDROCARBONS AS GASOLINE (TPHg), CONCENTRATIONS IN MILLIGRAMS PER KILOGRAM (mg/kg)
- ▽ STATIC GROUNDWATER LEVEL
- ND NOT DETECTED
- MONITORING WELL
 - BLANK
 - ▨ SCREENED INTERVAL
- * SOIL BORINGS PROJECTED ONTO B-B' CROSS-SECTION LINE FROM THEIR RESPECTIVE LOCATIONS
- TPHg CONCENTRATIONS >100 mg/kg IN SOIL
- SM SILTY SAND
- SC CLAYEY SAND
- SP POORLY GRADED SAND
- SP/SC POORLY GRADED SAND WITH CLAY
- SC/SM CLAYEY SAND WITH SILT



SECOR
INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

GEOLOGIC CROSS SECTION B-B'


SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CALIFORNIA

CAD FILE NO.: X-SECBB4

PROJECT No.:
080T.04926.00


DATE: 4/26/02

FIGURE: 7



LEGEND:

- SOIL SAMPLE LOCATION
- (2,100) TOTAL PETROLEUM HYDROCARBONS AS GASOLINE (TPHg), CONCENTRATIONS IN MILLIGRAMS PER KILOGRAM (mg/kg)
- ▽ STATIC GROUNDWATER LEVEL
- ND NOT DETECTED
- UST UNDERGROUND STORAGE TANK
- MONITORING WELL
 - BLANK
 - ▨ SCREENED INTERVAL
- TPHg CONCENTRATIONS >100 mg/kg IN SOIL
- SM SILTY SAND
- SC CLAYEY SAND
- SP POORLY GRADED SAND
- SP/SC POORLY GRADED SAND WITH CLAY



SECOR
INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

GEOLOGIC CROSS SECTION C-C'


SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CALIFORNIA

CAD FILE NO.: X-SECcc

PROJECT No.:
080T.04926.00

DATE: 4/16/02

FIGURE: 8



LEGEND:



SOIL BORING



GROUNDWATER MONITORING WELL



PROPERTY LINE



GAS



SEWER/STORM DRAIN




ELECTRIC LINE




TELEPHONE



WATER



GROUNDWATER FLOW DIRECTION AND GRADIENT



APPROXIMATE SCALE IN FEET

SECOR

INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

4/16/02

GROUNDWATER ELEVATION CONTOUR MAP -
FEBRUARY 19, 2002
SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CA.


PROJECT No.:

080T.04926.00

FIGURE: 9

DAVEYGW02.DWG

K:\ALLPROJECTS2003DWGS\GENERAL 2003\DAVEY PROPERTY\DAVEYGW02-02.DWG MODIFIED BY RSOTO ON MAR 17, 2003 - 14:43



LEGEND:


- SOIL BORING
- ⊕ GROUNDWATER MONITORING WELL
- - - - - PROPERTY LINE
- GAS
- SEWER/STORM DRAIN
- ELECTRIC LINE
- TELEPHONE
- WATER
- - - 10 - - - ESTIMATED EXTENT OF BENZENE CONCENTRATION IN GROUNDWATER.

($<50/<0.5/<0.5$)

TOTAL PETROLEUM HYDROCARBONS AS GASOLINE / BENZENE / METHYL-T-BUTYL ETHER CONCENTRATIONS IN MICROGRAMS PER LITER ($\mu\text{g/L}$)

WELLS (MW-1 THROUGH MW-7) SAMPLED ON FEBRUARY 19, 2002

BORINGS (B1-B3) SAMPLED ON JULY 2, 1996



SECOR

INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

**HYDROCARBON CONCENTRATIONS IN
GROUNDWATER - FEBRUARY 19, 2002**

SUSAN DAVEY PROPERTY
1279 & 1281 E. MAIN STREET
EL CAJON, CA.

PROJECT No.:

080T.04926.00

FIGURE: 10

Figure 11
Dissolved Benzene Concentration Trends
(MW-1)




Figure 12
Dissolved Benzene Concentration Trends
(MW-2)







Figure 13
Dissolved Benzene Concentration Trends
(MW-4)



S E C O R

APPENDICES

APPENDIX A
SOIL VAPOR LABORATORY REPORT
AND
CHAIN-OF-CUSTODY DOCUMENTATION



1/30/2002

SECOR
2655 Camino Del Rio North, Suite 302
San Diego, CA 92108

Project Name: 1279-1281 E. Main Street, El Cajon
Project No.: PO# 0804926 Susan Davy Property

Attention: Mr. Brain Demme

The following sample(s) were received and analyzed:

<u>Date Received</u>	<u>Quantity</u>	<u>Matrix</u>
1/22/02	12	Vapor


The samples were analyzed by one or more of the EPA methodologies or equivalent methods listed below.

VOCs -- EPA Method 8260

The results are included with a summary of the quality control procedures. Please note that the symbol "nd" indicates a value below the reporting limit for the particular compound in the sample.

Please feel free to call us to discuss any part of this report or to schedule future projects.

Sincerely,


Tamara Davis
Lab Director

Mobile One Laboratories is certified by the California Department of Health Services (certificate #s: 1194, 1561, 1921, 2088, 2278).

HP Labs Project # SE012202-L5

148 S. Vinewood Street • Escondido, CA 92029 • Phone (760) 735-3208 • Fax (760) 735-2469
432 N. Cedros Avenue • Solana Beach, CA 92075 • Phone (858) 793-0401 • Fax (858) 793-0404
2373 208th Street Suite F-1 • Torrance, CA 90501 • Phone (310) 782-2929 • Fax (310) 782-2798

Report Summary

EPA Method 8260B (5030 Prep.)

Client: SECOR

Project: 1279-1281 E. Main Street, El Cajon

Matrix: Vapor
Units: ug/L

Sample Name:

Analysis Date

Analysis Time

Dilution Factor:

Purge Volume(cc):

Compound

BLANK

22 Jan 2002

6:04 am

0.1

0.05

n/a

VP8-2

22 Jan 2002

8:12 am

0.05

30

VP8-5

22 Jan 2002

8:38 am

0.05

30

VP9-2

22 Jan 2002

9:03 am

0.05

30

VP9-5

22 Jan 2002

9:28 am

0.05

30

VP10-2

22 Jan 2002

9:53 am

0.05

30

Amount Found

Amount Found

Amount Found

Amount Found

Amount Found

Amount Found

Amount Found

Amount Found

Benzene

Toluene

Ethylbenzene

m,p-Xylene

o-Xylene

1

1

1

1

1

nd

nd

nd

1.8

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

nd

18

nd

1.7

1.9

nd

Surrogates

Spiked

50 ng

50 ng

50 ng

50 ng

QC Limits(% Rec.)

75-125

70-130

75-125

75-125

106

97

92

86

Percent Recovery

106

99

95

87

110

103

96

90

105

101

94

84

88


106

121

85

Analyses performed by: Jim Cook

SE012202-L5



Client: SECOR
Project: 1279-1281 E. Main Street, El Cajon

Sample Name: VP10-5 VP11-2 VP11-5 VP12-2 VP12-5 VP13-2
Analysis Date: 22 Jan 2002 22 Jan 2002 22 Jan 2002 22 Jan 2002 22 Jan 2002 22 Jan 2002
Analysis Time: 10:45 am 11:09 am 11:34 am 12:24 pm 12:50 pm 1:15 pm
Dilution Factor: 0.1 0.2 0.1 0.05 0.05 0.05
Purge Volume(cc): 30 30 30 30 30 30

Matrix: Vapor
Units: ug/L

E.Q.L. Amount Found Amount Found Amount Found Amount Found Amount Found Amount Found


Benzene	1	75	9.0	4.1	nd	nd
Toluene	1	1.3	1.4	4.1	2.4	2.3
Ethylbenzene	1	3.9	nd	1.2	nd	nd
m,p-Xylene	1	2.1	1.6	4.6	2.1	2.1
o-Xylene	1	nd	nd	nd	nd	nd

Surrogates Spiked QC Limits(% Rec.) Percent Recovery

DBFM	50 ng	75-125	84	92	99	97
1,2-DCA-d4	50 ng	70-130	102	101	89	91
Toluene - d8	50 ng	75-125	114	105	98	97
1,4-BFB	50 ng	75-125	81	83	86	86

Analyses performed by: Jim Cook

SE012202-L5



Matrix: Vapor
Units: ug/L

Client: SECOR
Project: 1279-1281 E. Main Street, El Cajon


Sample Name: VP13-5
Analysis Date: 22 Jan 2002
Analysis Time: 1:39 pm
Dilution Factor: 0.1 0.05
Purge Volume(cc): 30
Compound E.Q.L. Amount Found

Benzene	1	nd
Toluene	1	1.8
Ethylbenzene	1	nd
m,p-Xylene	1	1.9
o-Xylene	1	nd

Surrogates	Spiked	QC Limits(% Rec.)	Percent Recovery
DBFM	50 ng	75-125	100
1,2-DCA-d4	50 ng	70-130	92
Toluene - d8	50 ng	75-125	96
1,4-BFB	50 ng	75-125	87

Analyses performed by: Jim Cook

SE012202-L5



Calibration Verification

EPA Method 8260B

Client: SECOR
Project: 1279-1281 E. Main Street, El Cajon

Matrix: vapor
Units: ug/L

Sample Name: CCV
Analysis Date: 22 Jan 2002
Analysis Time: 5:40 am
Dilution Factor: 1

CCC
(-20 to +20%)
Pass

EPA 8260
(-20 to +20%)
Pass

Compound	Amount Found	Percent Diff	CCC (-20 to +20%) Pass	EPA 8260 (-20 to +20%) Pass
Dichlorodifluoromethane	47	-6		yes
Chloromethane	51	1		yes
Vinyl Chloride	57	14	yes	yes
Bromomethane	62	24		no
Chloroethane	49	-2		yes
Trichlorofluoromethane	48	-5		yes
1,1-Dichloroethene	47	-6	yes	yes
Methylene Chloride	51	2		yes
Methyl-t-butylether	37	-25		no
trans-1,2-Dichloroethene	51	1		yes
1,1-Dichloroethane	54	7		yes
2,2-Dichloropropane	55	10		yes
cis-1,2-Dichloroethene	48	-4		yes
Chloroform	53	7	yes	yes
Bromochloromethane	47	-7		yes
1,1,1-Trichloroethane	54	7		yes
1,1-Dichloropropene	47	-6		yes
Carbon Tetrachloride	51	1		yes
1,2-Dichloroethane	50	1		yes
Benzene	54	8		yes
Trichloroethene	47	-6		yes
1,2-Dichloropropane	47	-7	yes	yes
Bromodichloromethane	50	-1		yes
Dibromomethane	45	-9		yes
cis-1,3-Dichloropropene	37	-25		no
Toluene	49	-2	yes	yes
trans-1,3-Dichloropropene	39	-22		no
1,1,2-Trichloroethane	43	-14		yes
1,2-Dibromoethane	38	-24		no
1,3-Dichloropropane	43	-14		yes

Client: SECOR
Project: 1279-1281 E. Main Street, El Cajon

Matrix: vapor
Units: ug/L


EPA 8260
(-20 to +20%)

Sample Name:		CCV		Pass
Compound	Amount Found	Percent Diff		
Tetrachloroethene	48	-4	yes	
Dibromochloromethane	44	-12	yes	
Chlorobenzene	50	0	yes	
Ethylbenzene	50	0	yes	
1,1,1,2-Tetrachloroethane	53	5	yes	
m,p-Xylene	100	0	yes	
o-Xylene	50	0	yes	
Styrene	47	-6	yes	
Bromoform	42	-17	yes	
Isopropylbenzene	48	-5	yes	
1,1,2,2-Tetrachloroethane	41	-19	yes	
1,2,3-Trichloropropane	39	-23	no	
n-propylbenzene	49	-3	yes	
Bromobenzene	45	-11	yes	
1,3,5-Trimethylbenzene	47	-6	yes	
2-Chlorotoluene	50	0	yes	
4-Chlorotoluene	47	-6	yes	
tert-Butylbenzene	45	-10	yes	
1,2,4-Trimethylbenzene	49	-3	yes	
sec-Butylbenzene	48	-4	yes	
p-Isopropyltoluene	48	-4	yes	
1,3-Dichlorobenzene	47	-6	yes	
1,4-Dichlorobenzene	46	-7	yes	
n-Butylbenzene	48	-3	yes	
1,2-Dichlorobenzene	44	-13	yes	
1,2-Dibromo-3-chloropropane	34	-32	no	
1,2,4-Trichlorobenzene	42	-15	yes	
Hexachlorobutadiene	43	-15	yes	
Naphthalene	33	-35	no	
1,2,3-Trichlorobenzene	41	-19	yes	

CALIBRATION VERIFIED

Footnote Summary

<u>Footnote</u>	<u>Definition</u>
E.Q.L. nd J	Estimated Quantitation Limit Not detected above the E.Q.L. or detection limit. The concentration reported is between the Method Detection Limit and the E.Q.L.
D	Concentration reported from a secondary dilution; E.Q.L.s adjusted accordingly.
B	Analyte found in the associated blank.
E	Analyte amount exceeds calibration range. Amount quantitated by extrapolation.
***	MS/MSD, LCS/LCSD recovery is outside QC range; no corrective action taken.
M S	Surrogate recovery outside QC range due to matrix interference. Because of necessary sample dilution, value was outside QC limits.
& #	Gasoline range organics not identified as gasoline. Diesel range organics not identified as diesel.
**	This compound has been screened by EPA method 8020. Any positive results should be confirmed by a second analysis.



Chain of Custody Record

Date: JANUARY 22, 2002

148 S. Vinewood St., Escondido, CA 92029 • ph 760.735.3208 • fax 760.735.2469
432 N. Cedros Ave., Solana Beach, CA 92075 • ph 858.793.0401 • fax 858.793.0404
2373 208th Street Unit F, Torrance, CA 90501 • ph 310.782.2929 • fax 310.782.2798

HPL Project # SE 017202-LS

Outside Lab:

Client: SECOR Collector: DAVE BALKENBUSH Page: 1 of 1
Address: 2655 CAMINO DEL RIO NORTH, SUITE 302 Client Project # P080804926 Project Manager: BRIAN DEMME
SAN DIEGO, CA 92108 Location: 1277-1281 EAST MAIN STREET, EL CAJON
Phone: 619-296-6195 Fax: 619-296-6199 Turn around time:

Notes:

Sample	Depth	Time	Date	Sample Type	Container Type	TPH gasoline / diesel	TPH extended	8021 for BTEX/MTBE	8021 for Halogenated compounds	418.1 TRPH	8260B				VOCs and Oxygenates	Methane	Fixed Gases	Field Notes	Sample Receipt	Total # of containers
											Oxygenates	Oxygenates	Oxygenates	Oxygenates						
VP8-2	2'	0750	1/22/02	VACUUM	PLASTIC						X	X	X	X				P30cc	Intact: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Seal Intact: <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A Cold: <input type="checkbox"/> Yes <input type="checkbox"/> No N/A (Received on Site)	1
VP8-5	5'	0758									X	X	X	X				P30		1
VP9-2	2'	0812									X	X	X	X				P30		1
VP9-5	5'	0818									X	X	X	X				P30		1
VP10-2	2'	0842									X	X	X	X				P30		1
VP10-5	5'	0848									X	X	X	X				P30	SAMPLED P30cc RECEPTION	1
VP11-2	2'	0918									X	X	X	X				P30		1
VP11-5	5'	0928									X	X	X	X				P30		1
VP12-2	2'	0954									X	X	X	X				P30		1
VP12-5	5'	0958									X	X	X	X				P30		1
VP13-2	2'	1006									X	X	X	X				P30		1
VP13-5	5'	1010									X	X	X	X				P30		1

Relinquished by: (Signature) [Signature] (company) HPLabs Date: 1/22/02 Time: 10:40
Relinquished by: (Signature) [Signature] (company) Date: Date: Time: Time:
Relinquished by: (Signature) [Signature] (company) Date: Date: Time: Time:

*Signature constitutes authorization to proceed with analysis and acceptance of condition on back. ☐ Disposal @ \$2.00 each ☐ Return to client ☐ Pickup

APPENDIX B

SOIL VAPOR RISK CALCULATIONS
AND
DEPARTMENT OF LABOR STATISTICS

SITE ASSESSMENT & MITIGATION VAPOR RISK ASSESSMENT MODEL

Page 1-2

Input Data

Version: November 1999

Revised 01-08-2002

Case Name:

Susan Davey Property - Der Wienerschnitzel Restaurant Building

CHEMICAL OF CONCERN:

Enter Chemical Name = benzene

- | | |
|-------------------------------------|------------------------------------------|
| C11 benzene | E11 dichloromethane (methylene chloride) |
| C12 benzo(a)pyrene | E12 ethylbenzene |
| C13 carbon tetrachloride | E13 naphthalene |
| C14 chlorobenzene | E14 methyl tertiary butyl ether (MTBE) |
| C15 chloroethane (ethyl chloride) | E15 tetrachloroethene (PCE) |
| C16 chloromethane (methyl chloride) | E16 toluene |
| C17 1,2-dichlorobenzene | E17 1,1,1-trichloroethane |
| C18 1,3-dichlorobenzene | E18 1,1,2-trichloroethane |
| C19 1,4-dichlorobenzene | E19 trichloroethene (TCE) |
| C20 1,1-dichloroethene (1,1-DCE) | E20 trichloromethane (chloroform) |
| C21 trans-1,2-dichloroethene | E21 vinyl chloride |
| C22 1,1-dichloroethane (1,1-DCA) | E22 xylene |
| C23 1,2-dichloroethane (1,2-DCA) | |

Chemical Mixture (if app.) =

- C27 Gasoline
C28 Kerosene
C29 Diesel

- E27 Fuel Oil
E28 Waste Oil

If compound is not listed then data must be entered into the site-specific field.

SITE SPECIFIC INFORMATION			Site-Specific	Value Used
Mole fraction	dimensionless	MF		0.0000
Temperature	K	T		293
Water concentration (chemical)	ug/l	C _w		0
Soil concentration (chemical)	mg/kg	C _t		0
Soil concentration (TPH/TRPH)	mg/kg	C _t		0
Soil gas concentration (measured)	mg/m3 (ug/l)	C _{sg(m)}	5.17	5.17
Depth of contamination or Soil Gas	m	X	0.61	0.61

SITE ASSESSMENT & MITIGATION VAPOR RISK ASSESSMENT MODEL

Page 2-2

Data Input

Version: November 1999

Revised 12/20/2000

CHEMICAL PROPERTIES			Site Specific	Value Used
Henry's Law Constant	dimensionless	H		0.23
Vapor pressure	atm	VP		0.13
Molecular weight (chemical)	mg/mole	MW		78,110
Molecular weight (mixture)	mg/mole	MW(m)		#N/A
Universal gas constant	atm-m ³ /mole-K	R	XXXXXXXXXX	8.20E-05
Diffusion coefficient in air	cm ² /sec	D _a		0.088
Organic carbon partitioning coef.	cm ³ /gm	K _{oc}		62
SOIL PROPERTIES				
Total porosity	dimensionless	θ		0.3
Air-filled porosity	dimensionless	θ _a		0.2
Water-filled porosity	dimensionless	θ _w	XXXXXXXXXX	0.1
Bulk density (dry)	gm/cc	r _b		1.8
Weight fraction of organic carbon	dimensionless	foc		0.01
BUILDING SPECIFICATIONS				
Floor area of building	m ²	A		1
% of floor area that flux occurs	dimensionless			100%
Interior Height of building	m	R _h		2.44
Exchange rate of air	exchanges/hr	E		0.83
Attenuation factor(Crack factor)	dimensionless	S _b	0.1	0.1
OUTDOOR AIR COMPONENT				
Downwind contamination length	m	L		0
Wind speed	m/hr	u		16000
Height of building openings	m	h		2
EXPOSURE SCENARIO			Default values are for Industrial Uses	
Body weight	kg	BW		70
Inhalation rate	m ³ /day	IR		20
Exposure duration	yrs	ED	7	7
Hours per day	hr/day			12
Days per week	days/week			5
Weeks per year	weeks/yr			50
HEALTH RISK FACTORS				
Reference dose	mg/kg-day	RfD		0.0017
Slope factor (potency)	1/(mg/kg-day)	SF		0.1

Risk Calculations

Version: November 1999

Revised 01-08-2002

Case Name: Susan Davey Property - Der Wienerschnitzel Restaurant Building

Chemical: benzene

Variable Descriptions

Units

CALCULATION OF SOIL GAS CONCENTRATION

A. SOURCE - Free Product/Soil > 100mg/kg.

Mole fraction	MF	=	0.00E+00	dimensionless
Molecular weight	MW	=	7.81E+04	mg/mole
Vapor pressure	VP	=	1.30E-01	atm
Universal gas constant	R	=	8.20E-05	atm-m ³ /mole-K
Temperature	T	=	2.93E+02	K
Calculated soil gas concentration	C _{sg(fp)}	=	0.00E+00	mg/m ³

B. SOURCE - Groundwater

Water contamination level	C _w	=	0.00E+00	ug/l
Henry's Law Constant	H	=	2.30E-01	dimensionless
Calculated soil gas concentration	C _{sg(gw)}	=	0.00E+00	mg/m ³

C. SOURCE - Soil < 100 mg/kg

Soil contamination level	C _t	=	0.00E+00	mg/kg
Henry's Law Constant	H	=	2.30E-01	dimensionless
Bulk density (dry)	ρ _b	=	1.80E+00	gm/cc
Air-filled porosity	θ _a	=	2.00E-01	dimensionless
Water-filled porosity	θ _w	=	1.00E-01	dimensionless
Soil/water distribution coef.	K _d	=	6.20E-01	cm ³ /gm
Calculated soil gas concentration	C _{sg(s)}	=	0.00E+00	mg/m ³

D. SOURCE - Measured Soil Gas

Measured soil gas concentration	C _{sg(m)}	=	5.17E+00	mg/m ³ (ug/l)
---------------------------------	--------------------	---	----------	--------------------------

E. SOIL GAS CONCENTRATION USED IN RISK CALCULATIONS >>>> 5.17E+00 mg/m³

DIFFUSIVE TRANSPORT UPWARD IN UNSATURATED ZONE

Total porosity	θ	=	3.00E-01	dimensionless
Air-filled porosity	θ _a	=	2.00E-01	dimensionless
Diffusion coefficient in air	D _a	=	8.80E-02	cm ² /sec
Effective diffusion coefficient	D _e	=	4.60E-03	cm ² /sec
Depth of contamination or C _{sg}	X	=	6.10E-01	m
Calculated Flux	F _x	=	1.40E-02	mg/m ² -hour

Case Name: Susan Davey Property - Der Wienerschnitzel Restaurant Building

CALCULATING VAPOR CONCENTRATION IN BUILDING

A. INDOOR AIR COMPONENT

Floor area of building	A	=	1.00E+00	m2
% of floor area that flux occurs			1.00E+00	dimensionless
Attenuation factor(Crack factor)	S _b	=	1.00E-01	dimensionless
Flux area within building	A _f	=	1.00E-01	m2
Interior Height of building	R _h	=	2.44E+00	m
Volume of building	V	=	2.44E+00	m3
Exchange rate of air	E	=	8.30E-01	exchanges/hr
Ventilation rate	Q	=	2.03E+00	m3/hr
Indoor air component	C _i	=	6.93E-04	mg/m3

B. OUTDOOR AIR COMPONENT

Downwind contamination length	L	=	0.00E+00	m
Wind speed	u	=	1.60E+04	m/hr
Height of building openings (or height of breathing zone)	h	=	2.00E+00	m
Outdoor air component	C _o	=	0.00E+00	mg/m3

C. TOTAL INDOOR AIR CONCENTRATION

C _t	=	6.93E-04	mg/m3
----------------	---	----------	-------

EXPOSURE SCENARIO

Body weight	BW	=	7.00E+01	kg
Inhalation rate	IR	=	2.00E+01	m3/day
Exposure duration	ED	=	7.00E+00	hrs
Hours per day	conversion	=	1.20E+01	hr/day
Exposure time	ET	=	5.00E-01	hr/24 hours
Days per week	conversion	=	5.00E+00	days/week
Weeks per year	conversion	=	5.00E+01	weeks/yr
Exposure frequency	EF	=	2.50E+02	days/yr
Averaging Time (carc. risk)	AT	=	2.56E+04	days
Averaging Time (non-carc. risk)	AT	=	2.56E+03	days
Chemical Intake (carc. risk)	IT _c	=	6.78E-06	mg/kg-day
Chemical Intake (non-carc. risk)	IT _{nc}	=	6.78E-05	mg/kg-day

NON-CARCINOGENIC RISK (Chronic Risk)

Chemical Intake (non-carc. risk)	IT _{nc}	=	6.78E-05	mg/kg-day
Reference dose	RfD	=	1.70E-03	mg/kg-day
Hazard Index	HI	=	3.99E-02	

CARCINOGENIC RISK

Chemical Intake (carc. risk)	IT _c	=	6.78E-06	mg/kg-day
Slope factor (potency)	SF	=	1.00E-01	1/(mg/kg-day)
Cancer Risk	Risk	=	6.78E-07	



PS Home

OTHER AVAILABLE ECONOMIC NEWS RELEASES



Employee Tenure Summary

Technical information: (202) 691-6378
<http://www.bls.gov/cps/>

USDL 11-531

Media contact: 691-5902

For release: 10:00 A.M. EDT
Thursday, September 19, 2002

EMPLOYEE TENURE IN 2002

The median number of years that wage and salary workers had been with their current employer (referred to as employee tenure) was 3.7 years in January 2002, according to data released today by the Bureau of Labor Statistics of the U.S. Department of Labor. Since 1983, median employee tenure has ranged from 3.4 to 3.8 years in the years when such information was obtained.

Information on employee tenure is obtained from supplemental questions in the Current Population Survey (CPS). The CPS is a monthly survey of about 60,000 households that provides information on the labor force status, demographics, and other characteristics of the civilian noninstitutional population age 16 and over. The supplemental questions about employee tenure have been essentially the same since 1983. Prior to that year, the CPS questions on employee tenure were significantly different. As a result, this release focuses only on comparable data from 1983 to 2002. (See the Technical Note.) Some highlights from the January 2002 survey follow:

- Median years of tenure tend to increase with age. For example, the median tenure of older workers ages 55 to 64 was three and a half times that of workers ages 25 to 34.
- Thirty percent of workers age 25 and over had been with their current employer for 10 years or more at the time of the survey. For workers age 55 and over, half had such long tenure.
- The share of employed persons who had been with their employer for 12 months or less declined with age. Seventy percent of teenagers had been with their employer for a year or less, compared with 10 percent of persons age 55 and over.
- The median years of tenure for workers in the public sector was twice that of workers in the private sector. This is partly due to the relatively older age of the public-sector workforce.
- Managerial and professional specialty workers had the highest tenure among the major occupational groups, while workers in service occupations had the lowest median tenure.

Demographic characteristics

In January 2002, the median tenure (the point at which half of the workers had more tenure and half had less tenure) was 3.9 years for men and 3.4 years for women. Median tenure has been about one-half year higher for men than for women since 1996, compared with a difference of about one year in the prior survey years. (See table 1.)

- 2 -

Among men, median tenure changed little from February 2000 (when data on job tenure were last collected), but was slightly lower than in January 1983, despite an upward shift in the age of the male workforce. As shown

<http://stats.bls.gov/news.release/tenure.nr0.htm>

12/26/02

below, the percentage of male wage and salary workers who were between the ages of 35 and 54 increased in January 1983 to January 2002. All else held constant, this age shift would have been associated with an increase in median tenure because, until retirement age, tenure tends to increase with age. However, median tenure declined for men in most age groups, offsetting the aging effect.

For women, median tenure also changed little from February 2000, though it was higher than in January 1983. Contributing to the increased tenure was an upward shift in the age distribution of working women from 1983 to 2002. In addition, there has been some increase in tenure between the two time periods, particularly among women ages 40 to 49. For example, the proportion of women in this age group who had been with their employer for 10 years or more rose from 28 percent in 1983 to 33 percent in 2002.

Percent distribution of employed wage and salary workers by age and sex, January 1983 and January 2002

Age	Men		Women	
	January 1983	January 2002	January 1983	January 2002
Total, 16 years and over...	100.0	100.0	100.0	100.0
16 to 24 year.....	20.0	15.2	22.5	15.8
25 to 34 year.....	29.9	23.6	28.9	21.9
35 to 44 year.....	21.2	27.0	21.2	26.4
45 to 54 year.....	15.6	21.6	14.7	23.0
55 to 64 year.....	11.1	10.0	10.5	10.4
65 years and over.....	2.2	2.6	2.3	2.5

Note: Data exclude the incorporated and unincorporated self-employed.

In January 2002, 33 percent of male wage and salary workers age 25 and over had been with their current employer for 10 years or more, compared with 29 percent of women. The gap between men and women with such long tenure is about the same as when the survey was conducted in 1998 and 2000; however, it is about one-third lower than in 1983. (See table 2. Workers ages 16 to 24 are excluded from table 2 because few of these young workers could have been with their current employer for 10 years or more.)

Larger proportions of whites and blacks than of Hispanics had 10 or more years of tenure with their current employer. In January 2002, 22 percent of Hispanics (age 25 and over) had been with their current employer for 10 years or more, compared with 29 percent of blacks and 32 percent of whites. This discrepancy can be explained, in part, by the relative youth of the Hispanic workforce. For example, among persons age 25 and over, nearly two-fifths of employed Hispanics were between the ages of 25 and 34, compared with about one-fourth of employed whites and blacks. Moreover, about 1 in 10 employed Hispanics age 35 and over--the group more likely to have 10 or more years of tenure--had not been in the United States for 10 years at the time of the survey.

- 3 -

In January 2002, 25 percent of wage and salary workers age 16 and over had been with their current employer for 12 months or less, down slightly from 27 percent in February 2000. This group includes new entrants and reentrants to the workforce, job losers who found new jobs during the previous year, and workers who had voluntarily changed employers during the previous year. Young workers are more likely to have shorter tenure than older workers. For example, 72 percent of 16- to 19-year-olds and 51 percent of 20- to 24-year-olds had tenure of 12 months or less with their current employer; this compares with 11 percent of workers ages 55 to 64.

Industry

In January 2002, nonagricultural wage and salary workers in government had double the tenure of their counterparts in private industries, 6.7 and 3.3 years, respectively. (See table 5.) Differing age distributions can explain part of the gap in tenure, as government workers tend to be older than workers in private industries. For example, 74 percent of government workers were age 35 and over, compared with 61 percent of private wage and salary workers.

Within the private sector, manufacturing workers had the highest median tenure (5.5 years) of the major industry groups. Within manufacturing, industries with particularly high employee tenure included petroleum and coal products (10.2 years), primary metal industries (7.6 years), paper and allied products (7.4 years), and transportation equipment (7.0 years). Across the major industries, median tenure was lowest among workers in retail trade, at 2.2 years. Once again, age distributions affect overall median tenure. For example, workers in manufacturing tend to be older than those in retail trade.

Occupation

Managerial and professional specialty workers had the highest median tenure (4.8 years) among the major occupational groups. (See table 6.) Within this group, officials and administrators in public administration had a notably high median tenure of 11.3 years. Workers in service occupations had the lowest median tenure, 2.4 years. Within services, food service workers had the lowest median tenure (1.4 years), while protective service workers had the highest (5.1 years). Workers in service occupations tend to be younger than persons employed in managerial and professional specialty occupations.

▪ Employee Tenure Explanatory Note

▪ Table 1. Median years of tenure with current employer for employed wage and salary workers by age and sex, selected years, 1983-2002

▪ Table 2. Percent of employed wage and salary workers 25 years and over who had 10 years or more of tenure with their current employer by age and sex, selected years, 1983-2002

▪ Table 3. Distribution of employed wage and salary workers by tenure with current employer, age, sex, race, and Hispanic origin, January 2002

▪ Table 4. Median years of tenure with current employer for employed wage and salary workers 25 years and over by educational attainment, sex, and age, January 2002

▪ Table 5. Median years of tenure with current employer for employed wage and salary workers by industry, selected years, 1983-2002

▪ Table 6. Median years of tenure with current employer for employed wage and salary workers by occupation, selected years, 1983-2002

▪ Text version of entire news release

Table of Contents

www.dol.gov

[Frequently Asked Questions](#) | [Freedom of Information Act](#) | [Customer Survey](#)
[Privacy & Security Statement](#) | [Linking to Our Site](#) | [Accessibility Information](#)

U.S. Bureau of Labor Statistics
Division of Labor Force Statistics
Washington, DC 20212-0001

URL: <http://www.bls.gov/CPS>
Phone: (202) 691-6378
CPS data questions: cpsinfo@bls.gov
Technical (web) questions: webmaster@bls.gov
Other comments: feedback@bls.gov



Table 5. Median years of tenure with current employer for employed wage and salary workers, selected years, 1983-2002

Table 5. Median years of tenure with current employer for employed wage and salary worker 1983-2002

Industry	January 1983	January 1987	January 1991	February 1999
Total, 16 years and over.....	3.5	3.4	3.6	3.
Agriculture.....	2.2	2.4	2.6	3.
Nonagricultural industries.....	3.6	3.4	3.6	3.
Government.....	5.8	6.5	6.5	6.
Private industries.....	3.2	3.0	3.2	3.
Mining.....	3.4	6.1	5.8	6.
Construction.....	2.0	2.0	2.6	2.
Manufacturing.....	5.4	5.5	5.2	5.
Durable goods(1).....	5.6	6.0	5.8	5.
Lumber and wood products.....	4.0	3.2	3.6	3.
Furniture and fixtures.....	4.2	3.2	4.0	4.
Stone, clay, and glass products.....	7.0	6.8	6.3	5.
Primary metal industries.....	10.0	10.2	9.7	8.
Fabricated metal products.....	5.7	5.5	5.5	5.
Machinery and computing equipment.....	5.8	6.7	5.9	5.
Electrical machinery, equipment, and supplies....	4.7	4.8	5.5	4.
Transportation equipment(1).....	8.8	8.0	7.6	8.
Motor vehicles and equipment.....	13.0	11.2	11.7	7.
Aircraft and parts.....	6.4	6.8	6.3	9.
Professional and photographic equipment and watches.....	4.7	5.9	5.1	5.
Toys, amusements, and sporting goods.....	3.6	5.8	3.2	2.
Nondurable goods(1).....	5.1	4.9	4.7	5.
Food and kindred products.....	5.2	4.4	4.2	5.
Textile mill products.....	7.0	7.0	5.6	5.
Apparel and other finished textile products.....	3.8	3.2	3.8	3.
Paper and allied products.....	7.6	8.6	7.6	8.
Printing and publishing.....	3.2	3.2	3.5	4.
Chemicals and allied products.....	7.0	7.2	5.7	6.
Petroleum and coal products.....	6.0	11.7	8.4	10.
Rubber and miscellaneous plastics products.....	5.4	4.4	4.7	4.
Transportation and public utilities.....	5.8	5.7	5.8	5.
Transportation.....	4.6	3.9	4.2	4.
Communications and other public utilities.....	8.3	8.4	9.9	8.
Wholesale trade.....	3.8	3.7	3.4	3.
Retail trade.....	1.9	1.8	1.9	1.
Finance, insurance, and real estate.....	3.2	3.0	3.4	4.
Banking and other finance.....	3.3	3.1	3.6	3.
Insurance and real estate.....	3.0	2.9	3.2	4.
Services(1).....	2.5	2.5	2.7	3.
Private households.....	1.8	1.7	1.9	2.
Services, except private households.....	2.5	2.5	2.7	3.
Business services.....	1.5	1.6	1.8	2.

Automobile and repair services.....	2.0	2.0	2.1	2.
Personal services except private households.....	2.0	2.0	2.1	2.
Entertainment and recreation services.....	1.8	1.8	2.3	1.
Hospitals.....	3.5	4.6	4.2	5.
Health services, except hospitals.....	2.5	2.4	2.7	2.
Educational services.....	2.7	3.1	3.5	3.
Social services.....	2.2	2.3	2.3	2.
Other professional services.....	2.9	2.8	3.3	3.

1 Includes other industries, not shown separately.

r =revised.

NOTE: Data for 1996, 1998, 2000, and 2002 are not strictly comparable with data for 199 population controls from the 1990 census, adjusted for the estimated undercount, are used for the 1983-91 period are based on population controls from the 1980 census. Also, begin incorporate the effects of the redesign of the Current Population Survey introduced in Jan incorporated and unincorporated self-employed.

Table of Contents

[Back to Top](#)

www.dol.gov

[Frequently Asked Questions](#) | [Freedom of Information Act](#) | [Customer Survey](#)
[Privacy & Security Statement](#) | [Linking to Our Site](#) | [Accessibility Information](#)

Bureau of Labor Statistics
Division of Labor Force Statistics
Suite 4675
Massachusetts Avenue, NE
Washington, DC 20212-0001

URL: <http://www.bls.gov/CPS>
Phone: (202) 691-6378
CPS data questions: cpsinfo@bls.gov
Technical (web) questions: webmaster@bls.gov
Other comments: feedback@bls.gov

Table 5. Median years of tenure with current employer for employed wage and salary workers by industry, selected years, 1983-2002

Table 5. Median years of tenure with current employer for employed wage and salary workers by industry, selected years, 1983-2002

Industry	January 1983	January 1987	January 1991	February 1996	February 1998	February 2000	January 02
Total, 16 years and over.....	3.5	3.4	3.6	3.8	3.6	3.5	3.7
Agriculture.....	2.2	2.4	2.6	3.4	2.9	3.1	3.4
Nonagricultural industries.....	3.6	3.4	3.6	3.8	3.6	3.5	3.7
Government.....	5.8	6.5	6.5	6.9	7.3	7.2	6.7
Private industries.....	3.2	3.0	3.2	3.3	3.2	3.2	3.3
Mining.....	3.4	6.1	5.8	6.1	5.6	6.5	4.6
Construction.....	2.0	2.0	2.6	2.9	2.7	2.8	3.0
Manufacturing.....	5.4	5.5	5.2	5.4	4.9	5.0	5.5
Durable goods(1).....	5.6	6.0	5.8	5.3	4.9	4.9	5.5
Lumber and wood products.....	4.0	3.2	3.6	3.3	3.8	4.0	3.5
Furniture and fixtures.....	4.2	3.2	4.0	4.2	3.9	4.1	5.3
Stone, clay, and glass products.....	7.0	6.8	6.3	5.1	6.1	5.4	5.9
Primary metal industries.....	10.0	10.2	9.7	8.1	8.0	7.0	7.6
Fabricated metal products.....	5.7	5.5	5.5	5.1	4.0	4.7	5.5
Machinery and computing equipment.....	5.8	6.7	5.9	5.2	4.4	4.5	.5
Electrical machinery, equipment, and supplies....	4.7	4.8	5.5	4.9	5.0	4.7	4.9
Transportation equipment(1).....	8.8	8.0	7.6	8.3	7.8	6.4	7.0
Motor vehicles and equipment.....	13.0	11.2	11.7	7.8	6.4	5.8	7.0
Aircraft and parts.....	6.4	6.8	6.3	9.8	9.6	9.7	8.3
Professional and photographic equipment and watches.....	4.7	5.9	5.1	5.1	5.5	5.2	4.5
Toys, amusements, and sporting goods.....	3.6	5.8	3.2	2.7	3.6	3.7	5.6
Nondurable goods(1).....	5.1	4.9	4.7	5.4	4.9	5.1	5.5
Food and kindred products.....	5.2	4.4	4.2	5.1	5.1	5.0	5.1
Textile mill products.....	7.0	7.0	5.6	5.4	6.7	7.4	5.1
Apparel and other finished textile products.....	3.8	3.2	3.8	3.8	3.8	3.3	4.8
Paper and allied products.....	7.6	8.6	7.6	8.4	7.5	6.1	7.4
Printing and publishing.....	3.2	3.2	3.5	4.3	4.0	4.4	5.1
Chemicals and allied products.....	7.0	7.2	5.7	6.9	5.4	5.8	6.3
Petroleum and coal products.....	6.0	11.7	8.4	10.3	9.4	7.5	10.2

Transportation and public utilities.....	5.8	5.7	5.8	5.2	4.8	4.4	4.4
Transportation.....	4.6	3.9	4.2	4.1	3.8	3.9	4.3
Communications and other public utilities.....	8.3	8.4	9.9	8.2	8.2	5.2	4.7
Wholesale trade.....	3.8	3.7	3.4	3.9	4.1	3.9	3.9
Retail trade.....	1.9	1.8	1.9	1.9	1.8	2.0	2.2
Finance, insurance, and real estate.....	3.2	3.0	3.4	4.1	3.5	3.6	3.6
Banking and other finance.....	3.3	3.1	3.6	3.9	3.7	3.3	3.5
Insurance and real estate.....	3.0	2.9	3.2	4.2	3.4	3.9	3.8
Services(1).....	2.5	2.5	2.7	3.0	2.9	2.9	3.1
Private households.....	1.8	1.7	1.9	2.3	2.3	2.9	2.8
Services, except private households.....	2.5	2.5	2.7	3.0	2.9	2.9	3.1
Business services.....	1.5	1.6	1.8	2.0	1.9	r1.8	2.2
Automobile and repair services.....	2.3	2.0	2.2	2.9	2.4	2.7	3.0
Personal services, except private households.....	2.0	2.0	2.1	2.3	2.3	2.7	8
Entertainment and recreation services.....	1.8	1.8	2.3	1.9	1.9	2.3	4.1
Hospitals.....	3.5	4.6	4.2	5.2	5.2	5.2	4.8
Health services, except hospitals.....	2.5	2.4	2.7	2.9	2.9	3.2	3.0
Educational services.....	2.7	3.1	3.5	3.8	3.5	3.3	3.6
Social services.....	2.2	2.3	2.3	2.8	2.7	2.6	2.7
Other professional services.....	2.9	2.8	3.3	3.5	3.3	r3.2	3.5

1 Includes other industries, not shown separately.

r =revised.

NOTE: Data for 1996, 1998, 2000, and 2002 are not strictly comparable with data for 1991 and earlier years because population controls from the 1990 census, adjusted for the estimated undercount, are used beginning in 1996. Figures for the 1993-91 period are based on population controls from the 1980 census. Also, beginning in 1996, the figures incorporate the effects of the redesign of the Current Population Survey introduced in January 1994. Data exclude the incorporated and unincorporated self-employed.

Table of Contents

[Back to Top](#)

[Frequently Asked Questions](#) | [Freedom of Information Act](#) | [Customer Survey](#)
[Privacy & Security Statement](#) | [Linking to Our Site](#) | [Accessibility Information](#)

Phone: (202) 637-6378
CPS data questions: cpsinfo@bls.gov
Technical (web) questions: webmaster@bls.gov
Other comments: feedback@bls.gov

Div: [redacted] Lab: [redacted] Se St: [redacted]
Suite 4675
2 Massachusetts Avenue, NE
Washington, DC 20212-0001

Table 6. Median years of tenure with current employer for employed wage and salary workers by occupation, selected years, 1983-2002

Table 6. Median years of tenure with current employer for employed wage and salary workers by occupation, selected years, 1983-2002

Occupation	January 1983	January 1987	January 1991	February 1996	February 1998	February 2000	January 2002
Total, 16 years and over.....	3.5	3.4	3.6	3.8	3.6	3.5	3.7
Managerial and professional specialty.....	4.8	5.0	5.2	5.1	4.8	4.8	4.8
Executive, administrative, and managerial.....	5.3	5.1	5.5	5.5	5.3	5.0	5.3
Officials and administrators, public administration..	8.4	9.7	10.7	10.4	12.3	12.0	11.3
Other executive, administrative, and managerial.....	5.3	5.2	5.7	5.6	5.5	5.2	5.4
Management-related occupations.....	4.8	4.2	4.7	4.8	4.1	3.9	4.3
Professional specialty.....	4.5	5.0	4.9	4.8	4.4	4.6	4.3
Engineers.....	6.3	6.1	6.7	6.6	5.3	4.8	4.8
Mathematical and computer scientists.....	7.8	5.0	4.2	4.5	7.7	7.7	7.7
Natural scientists.....	4.7	6.0	5.6	4.4	5.0	5.2	4.6
Health diagnosing occupations.....	2.8	2.5	3.0	3.3	3.2	3.4	4.1
Health assessment and treating occupations.....	3.6	4.1	4.2	4.9	4.6	5.3	4.6
Teachers, college and university.....	4.4	7.2	5.5	4.4	4.2	4.7	3.8
Teachers, except college and university.....	6.0	7.0	6.7	5.8	5.9	5.6	5.0
Lawyers and judges.....	3.2	3.3	3.4	4.3	4.3	3.8	4.7
Other professional specialty occupations.....	3.4	3.5	3.6	3.9	3.6	3.9	.9
Technical, sales, and administrative support.....	3.1	2.9	3.2	3.4	3.2	3.1	3.2
Technicians and related support.....	3.3	3.8	3.8	4.7	4.3	3.8	3.7
Health technologists and technicians.....	3.3	4.4	3.5	4.5	4.5	3.8	3.6
Engineering and science technicians.....	3.9	4.7	4.0	5.5	4.0	4.1	4.0
Technicians, except health, engineering, and science.	2.7	2.9	3.9	4.4	4.1	3.4	3.7
Sales occupations.....	2.3	2.3	2.4	2.5	2.4	2.7	2.7
Supervisors and proprietors.....	4.4	4.4	4.9	4.8	4.8	4.7	4.6
Sales representatives, finance and business services.	2.6	2.4	2.7	3.3	2.7	2.8	3.1
Sales representatives, commodities, except retail....	3.7	3.9	3.4	3.8	4.1	4.3	4.1
Sales workers, retail and personal services.....	1.6	1.4	1.4	1.3	1.2	1.4	1.5
Sales-related occupations.....	1.7	2.4	3.8	1.5	2.4	3.7	2.3
Administrative support, including clerical.....	3.5	3.3	3.6	4.0	3.6	3.4	3.6
Supervisors.....	7.6	8.9	8.4	9.4	8.2	7.6	7.5
Computer equipment operators.....	3.2	3.0	3.8	4.8	4.1	2.9	3.4
Secretaries, stenographers, and typists.....	3.2	3.0	3.4	4.4	4.1	4.4	4.3

Other administrative support, including clerical.....	3.2	4.6	5.9	7.3	7.6	9.4	9.9
Service occupations.....	2.2	2.0	2.3	2.4	2.4	2.5	2.4
Private household.....	1.9	1.9	2.2	2.2	2.3	2.8	2.9
Protective service.....	4.6	5.0	4.4	5.2	5.4	5.7	5.1
Service, except private household and protective.....	2.0	1.8	2.0	2.1	2.1	2.2	2.1
Food service.....	1.5	1.3	1.4	1.3	1.3	1.5	1.4
Health service.....	2.6	2.2	2.4	2.8	2.8	3.1	2.4
Cleaning and building service.....	3.0	2.7	3.0	3.0	3.1	3.2	3.1
Personal service.....	1.9	1.9	2.1	2.2	2.2	2.3	2.4
Precision production, craft, and repair.....	4.8	4.7	4.8	4.9	4.6	4.3	4.4
Mechanics and repairers.....	5.2	5.8	5.0	5.3	4.9	4.7	4.6
Construction trades.....	3.2	2.6	3.2	3.5	3.4	3.1	3.3
Other precision production, craft, and repair.....	6.0	6.2	6.4	6.3	6.1	5.4	6.7
Operators, fabricators, and laborers.....	3.9	3.4	3.5	3.2	3.2	3.2	5
Machine operators, assemblers, and inspectors.....	4.8	4.3	4.4	4.1	3.9	4.0	4.9
Transportation and material moving occupations.....	4.4	4.1	3.9	3.9	3.8	3.7	3.6
Motor vehicle operators.....	3.5	3.2	3.2	3.4	3.4	3.5	3.4
Other transportation and material moving occupations.....	6.8	7.2	6.3	5.4	4.8	4.8	4.6
Handlers, equipment cleaners, helpers, and laborers.....	2.1	2.0	2.2	1.9	1.9	2.0	2.4
Construction laborers.....	2.0	1.3	2.4	2.2	1.6	2.6	2.3
Other handlers, equipment cleaners, helpers, and laborers.....	2.2	2.2	2.1	1.8	1.9	1.9	2.4
Farming, forestry, and fishing.....	2.3	2.4	2.7	3.7	2.8	3.1	3.1
Farm operators and managers.....	3.9	5.0	4.8	6.2	4.7	3.9	5.5
Other farming, forestry, and fishing occupations.....	2.3	2.3	2.6	3.6	2.8	3.1	3.0

NOTE: Data for 1996, 1998, 2000, and 2002 are not strictly comparable with data for 1991 and earlier years because population controls from the 1990 census, adjusted for the estimated undercount, are used beginning in 1996. Figures for the 1983-91 period are based on population controls from the 1980 census. Also, beginning in 1996, the figures incorporate the effects of the redesign of the Current Population Survey introduced in January 1994. Data exclude the incorporated and unincorporated self-employed.

Table of Contents

[Back to Top](#)

[Frequently Asked Questions](#) | [Freedom of Information Act](#) | [Customer Survey](#)
[Privacy & Security Statement](#) | [Linking to Our Site](#) | [Accessibility Information](#)

Phone: (202) 551-0378
CPS data questions: cpsinfo@bis.gov
Technical (web) questions: webmaster@bis.gov
Other comments: feedback@bis.gov

Divis Labo a Sta
Suite 4675
2 Massachusetts Avenue, NE
Washington, DC 20212-0001

APPENDIX C
DRILLING PERMIT COVER SHEET



PERMIT # W100212

A.P.N. # 489-390-13

EST # H03126-001

**COUNTY OF SAN DIEGO
DEPARTMENT OF ENVIRONMENTAL HEALTH
LAND AND WATER QUALITY DIVISION**

MONITORING WELL AND BORING CONSTRUCTION AND DESTRUCTION PERMIT

SITE NAME: SUSAN DAVEY / WURZELL ESTATE PROPERTY

SITE ADDRESS: 1279-1281 E. MAIN STREET, EL CAJON, CA 92021

PERMIT FOR: 3 BORINGS

PERMIT APPROVAL DATE: DECEMBER 10, 2001

PERMIT EXPIRES ON: APRIL 9, 2002

PERMIT CONDITIONS:

1. All borings must be sealed from the bottom of the boring to the ground surface with an approved sealing material as specified in California Well Standards Bulletin 74-90, Part III, Section 19.D. **Drill cuttings are not an acceptable fill material.**
2. Placement of any sealing material at a depth greater than 30 feet must be done using the tremie method.
3. All wash water must be contained and disposed of properly.
4. All water and soil that is placed in drums must be labeled and stored as specified in the SAM Manual in Section 5, Page 7, (5.)
5. Within 60 days of completing work, submit a well/boring construction report, including all well and/or boring logs and laboratory data to the Well Permit Desk. This report must include all items required by the SAM Manual, Section 5, Pages 6 & 7.
6. This office must be given 48-hour notice of any drilling activity on this site and advanced notification of drilling cancellation. Please contact the Well Permit Desk at 338-2339.

NOTE: This permit does not constitute approval of a work plan as defined in Section 2722 of Article 11 of C.C.R., Title 23. Work plans are required for all unauthorized release investigations in San Diego County.

APPROVED BY:

M Crystal
MARISUE CRYSTAL

DATE: 12/10/2001

NOTIFIED:

12/10/01 *MBC*

APPENDIX D
METHODS AND PROCEDURES

APPENDIX D -- METHODS AND PROCEDURES

D.1 DRILLING AND SOIL SAMPLING PROCEDURES

Subsurface soil samples were collected by mechanical drilling methods using a truck-mounted drilling rig capable of drilling by continuous-flight hollow-stem auger (HSA) method. HSA methods are used when large-diameter or deep borings are required to investigate the subsurface and/or to install groundwater monitoring wells. Soil samples are collected as explained below.

In HSA drilling method, the augers and bits are decontaminated before and between borings by steam-cleaning to prevent cross-contamination by the drilling equipment. According to current SAM guidelines, equipment wash water must be contained on-site until laboratory results are available. Soil cuttings are contained in 55-gallon drums and labeled with respect to contents, origin, and contact person information.

During HSA drilling, soil samples are generally collected at five-foot intervals and at lithologic changes by driving a cylindrical sampler 18 inches into undisturbed soil beneath the base of the augers. When the sampler has reached its maximum penetration, it is withdrawn from the borehole and disassembled. Soil samples are retained and packaged, and the sampler is decontaminated by first scrubbing with a low-phosphate detergent solution, then rinsing with tap water, followed by deionized water.

In this soil sampling method, a portion of each sample is packed in a glass jar or a brass tube with TeflonTM-lined lid or end caps. In most cases, the brass or stainless steel tubes are inserted within the sampler and packed with soil as the sampler is driven into the soils. Samples are labeled with respect to location, depth, and date, and then signed and sealed by the sampler. Samples are then entered onto a chain-of-custody form and preserved on ice or refrigerated until delivery to the analytical laboratory.

Field screening for the presence of volatile organic compounds is accomplished with a Foxboro Model 128 organic vapor analyzer (OVA) or photoionization detector (PID). To screen for organic vapors, a soil portion is placed in a one-quart sealable plastic bag, desegregated, and exposed to direct sunlight, which allows soil vapors to collect in the air space of the sealed bag. After a short period of time (five to ten minutes), the bag is pierced with the probe and the reading is recorded. The OVA is calibrated to methane or the PID is calibrated to isobutylene at the beginning of the day. The reading is an indication of the concentration of the volatile organic compounds in the soil sample relative to similar samples analyzed under the same conditions. OVA and PID readings for each bagged sample are noted on the boring and monitoring well logs.

All soil borings, mechanical or manual, are either permitted with the County of San Diego Department of Health Services for drilling deeper than 20 feet, for conditions where groundwater will be encountered, or to construct groundwater/vadose zone monitoring wells, or they are abandoned in accordance with California Department of Water Resources Bulletins 74-81 and 74-90.

D.2 DECONTAMINATION PROCEDURES

Drilling equipment was either steam cleaned or washing with a high-pressure spray. Equipment which was used for sampling and which was in direct contact with soil or groundwater underwent a stringent decontamination process. The procedures are as follows:

- Brush off loose dirt with a bristle brush or cloth in the decontamination area so no visible residuals remain.
- Using scrub brushes, wash equipment in a solution consisting of non-phosphate detergent and tap water.
- Rinse equipment in tap water.
- As the final step, rinse equipment with distilled water and allow to air dry.

D.3 GROUNDWATER MONITORING WELL CONSTRUCTION AND DEVELOPMENT PROCEDURES

Groundwater monitoring well construction is completed through the annular space of the eight- or ten-inch-diameter continuous-flight hollow-stem augers. Well construction details include extending a two-inch diameter polyvinyl chloride (PVC) casing from bottom of the borehole to the surface. The casing is factory perforated with 0.02 inch wide slots from the bottom of the borehole to approximately five feet above the water table. The remainder of the casing to the surface is unperforated. A filter pack of #3 commercially graded sand extends from the bottom of the borehole to approximately three feet above the perforated casing. To construct the well and prevent the borehole from collapsing, the augers are withdrawn from the subsurface as the sand pack and bentonite seal are placed within the annular space of the augers. When the sand pack has been placed, the well is then surged for a minimum of five minutes to settle the sand pack. Additional sand is then added if necessary to complete the construction according to specifications. The annular space is then sealed with three feet of hydrated bentonite clay. The remainder of the well is filled with cement grout. Above the grout, a locking, water-tight traffic-rated well cover is set in concrete to protect and secure the wellhead.

Following construction, the monitoring wells are developed by surging and bailing. Development continues until sand-free water is produced. Water quality parameters such as pH, conductivity and temperature are measured during development to insure that formational water is entering the well. Three to five borehole volumes of water are typically removed from the wells during development.

D.4 GROUNDWATER MONITORING WELL SAMPLING PROCEDURES

The following procedures for well sampling were developed after the SAM's publication entitled. Site Assessment and Mitigation (SA/M) Manual", dated January 1996, and updated for 2000 and 2002.

- A. Using a decontaminated instrument (i.e., an interface probe), measure the depth to groundwater in reference to the measuring point at the top of the casing. Measure the total depth of the well to determine the height and volume of water in the well casing and borehole and record the measurements on the SECOR Monitoring Well Gauging Log form.
- B. Decontaminate PVC and/or Teflon™ bailers by scrubbing with a long handled brush in a low-phosphate detergent solution, followed by a tap water rinse and then a deionized water rinse.
- C. Utilize dedicated extraction tubing (lift pumps) or decontaminated pumping equipment (submersible pumps), as appropriate, to prepare pumping equipment for well purging.

D. Conduct field measurements for temperature, pH, and conductivity after approximately one borehole volume has been purged, or if the water level in the well is so low as to prevent further purging (i.e., the well is dry).

1) If the well has not been purged dry, continue to bail and/or pump an additional one-half borehole volume and conduct field measurements again.

a) If the first and second series of measurements vary by less than ten percent, the well has been adequately purged. Allow the well to recover to 80 percent of its static condition and begin the sampling procedure.

b) If the measurements vary by ten percent or greater, repeat Step D1 above.

2) If the well has been purged dry, measure the water level and allow the well to recharge to 80 percent of its static condition, or for two hours, whichever occurs first. Calculate the percent recovery.

a) If the well recovers less than 80 percent within two hours, it is a slow recharging well. Begin the sampling procedure.

b) If the well recovers to 80 percent or more within two hours, it is a fast recharging well. Repeat Step D1 above.

E. After adequate recharge of monitoring wells (approximately 80 percent recovery from maximum drawdown or after two hours if less than 80 percent is observed), use the decontaminated bailer to collect the groundwater sample.

F. Transfer the groundwater sample into the appropriate sample container(s) for the analyte to be tested, and label each sample using completed sample labels.

G. Discard or dedicate the bailer cord or pump tubing and repeat bailer/pumping equipment decontamination procedures in preparation of sampling the next well.

H. Complete Well Purging/Sampling Log forms for each well sampled and the chain-of-custody record.

I. When requested by client, collect field and trip blank samples of deionized water to check decontamination procedures. Additional and/or alternate field QA/QC samples can be collected and analyzed upon request.

J. Enter the sample onto the chain-of-custody form and preserve on ice in cooler until delivery to the analytical laboratory. Package samples for shipping; check each sample for proper labeling. Include the samples and custody paperwork in the cooler shipped to the laboratory.

APPENDIX E
BOREHOLE LOGS AND LEGEND

SECOR

BOREHOLE LOG

Number:

SB-4

Client:

Mr. Richard Reid

Job No:

08OT.04926.00

Sheet:

1 of 1

Location:

Susan Davey Property
1279/ 1281 East Main Street
El Cajon, CA

Drilling Company/Driller:

Tri-County Drilling, Inc.

SECOR Rep:

Brian Demme

Approved by:

CR Block

Date Started:

3/5/02

Date Finished:

3/5/02

Drill Rig/Sampling Method:

CME 75/ Hollow Stem Auger/ Continuous Core Barrel

Borehole Dia.:

8"

Casing Dia.:

NA

Surface Elevation:

NA

SAMPLE LOG

BOREHOLE LOG

Sample Number	OVA/PID (ppm)	Lab Results TPH(ppm)	Density Blows/ft	Depth in Feet	USCS Symbol	Graphic Log	Geologic Description (Soil Type, Color, grain, minor soil component, moisture, density, odor, etc.)	Backfill Detail
				0			Covered by: Asphalt (4") Base (4")	
				1				
				2	SM		Silty SAND, moderate brown (5YR 3/4), fine grained, moist, dense, slight hydrocarbon (HC) odor.	
				3				
				4				
SB-4/5'	10	<0.5		5				
				6				
				7				
				8				
				9				
SB-4/10'	1,000	80		10			Becomes grayish brown (5YR 3/2). Strong HC odor.	
				11				
SB-4/12'	1,000	1,400		12			Becomes moderate brown (5YR 3/4). Very dense.	
				13				
				14				
				15				
				16				
				17				
				18				
				19				
				20				
				21				
				22				
				23				
				24				
				25				
				26				
				27				
				28				
				29				
				30				

TOTAL DEPTH DRILLED = 12' BGS

Borehole backfilled bentonite chips and capped with concrete.

SECOR

BOREHOLE LOG

Number:

SB-5

Client:

Mr. Richard Reid

Job No:

08OT.04926.00

Sheet:

1 of 1

Location:

Susan Davey Property
1279/ 1281 East Main Street
El Cajon, CA

Drilling Company /Driller:

Tri-County Drilling, Inc.

SECOR Rep:

Brian Demme

Approved by:

CR Hollock

Date Started:

3/5/02

Date Finished:

3/5/02

Drill Rig/Sampling Method:

CME 75/ Hollow Stem Auger/ Continuous Core Barrel

Borehole Dia.:

8"

Casing Dia.:

NA

Surface Elevation:

NA


SAMPLE LOG





BOREHOLE LOG

Sample Number	OVA/PID (ppm)	Lab Results TPH(ppm)	Density Blows/ft	Depth in Feet	USCS Symbol	Graphic Log	Geologic Description (Soil Type, Color, grain, minor soil component, moisture, density, odor, etc.)	Backfill Detail
				0			Covered by: Asphalt (4") Base (4")	
				1				
				2	SM		Silty SAND, moderate brown (5YR 3/4), fine grained, trace coarse sand, weathered concrete, brick, moist, no hydrocarbon (HC) odor.	
				3				
				4				
SB-5/5'	0.0	<0.5		5				
				6				
				7				
				8				
				9				
SB-5/10'	1,000	960		10			Becomes strong HC odor.	
				11				
SB-5/12'	1,000	1,800		12				
				13				
				14				
				15				
				16				
				17				
				18				
				19				
				20				
				21				
				22				
				23				
				24				
				25				
				26				
				27				
				28				
				29				
				30				

















TOTAL DEPTH DRILLED = 12' BGS

Borehole backfilled bentonite chips and capped with concrete.

SECOR				BOREHOLE LOG				Number: SB-6		
				Client: Mr. Richard Reid			Job No: 08OT.04926.00		Sheet: 1 of 1	
				Location: Susan Davey Property 1279/ 1281 East Main Street El Cajon, CA			Drilling Company/Driller: Tri-County Drilling, Inc.			
SECOR Rep: Brian Demme		Approved by: 		Drill Rig/Sampling Method: CME 75/ Hollow Stem Auger/ Continuous Core Barrel				Borehole Dia.: 8"	Casing Dia.: NA	Surface Elevation: NA
Date Started: 3/5/02		Date Finished: 3/5/02								

SAMPLE LOG				BOREHOLE LOG				
Sample Number	OVA/PID (ppm)	Lab Results TPH(ppm)	Density Blows/ft	Depth in Feet	USCS Symbol	Graphic Log	Geologic Description (Soil Type, Color, grain, minor soil component, moisture, density, odor, etc.)	Backfill Detail
				0			Covered by: Grass (6")	
				1	SM/SC		Silty SAND, moderate brown (5YR 3/4), fine grained, dry to moist, medium dense, no hydrocarbon (HC) odor. Borderline silt or clay.	
				2				
				3				
				4				
SB-6/5'	0.0	<0.5		5				
				6				
				7				
				8				
				9	SM		Silty SAND, moderate brown (5YR 4/4), fine grained, trace fine gravel, moist, dense, no HC odor.	
				10				
				11				
SB-6/10'	0.0	<0.5		12				
				13				
SB-6/12'	0.0	<0.5		14				
				15			TOTAL DEPTH DRILLED = 12' BGS Borehole backfilled bentonite chips and capped with concrete.	
				16				
				17				
				18				
				19				
				20				
				21				
				22				
				23				
				24				
				25				
				26				
				27				
				28				
				29				
				30				

DEFINITION OF TERMS

PRIMARY DIVISIONS			GRAPHIC SYMBOL	GROUP SYMBOL	SECONDARY DIVISIONS
COARSE GRAINED SOILS More Than Half Of Material Is Larger Than No. 200 Sieve Size	GRAVELS More Than Half Of Coarse Fraction Is Larger Than No. 4 Sieve	Clean Gravels (Less Than 5% Fines)		GW	Well graded gravels, gravel-sand mixtures, little or no fines.
		Gravel With Fines		GP	Poorly graded gravels or gravel-sand mixtures, little or no fines.
				GM	Clayey gravels, gravel-sand-clay mixtures, non-plastic fines.
				GC	Clayey gravels, gravel-sand-clay mixtures, plastic fines.
	SANDS More Than Half Of Coarse Fraction Is Smaller Than No. 4 Sieve	Clean Sands (Less Than 5% Fines)		SW	Well graded sands or gravelly sands, little or no fines.
		Sands With Fines		SP	Poorly graded sands or gravelly sands, little or no fines.
				SM	Silty sands, sand-silt mixtures, plastic fines.
				SC	Clayey sands, sand-clay mixtures, plastic fines.
FINE GRAINED SOILS More Than Half Of Material Is Smaller Than No. 200 Sieve Size	SILTS AND CLAYS Liquid Limit Is Less Than 50%		ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity.	
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays.	
			OL	Organic silts and organic silty clays of low plasticity.	
	SILTS AND CLAYS Liquid Limit Is Greater Than 50%		MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts.	
			CH	Inorganic clays of high plasticity, fat clays.	
			OH	Organic clays of medium to high plasticity, organic silts.	
	HIGHLY ORGANIC SOILS			Pt	Peat and other highly organic soils.
			Dg	Decomposed granite.	

SECOR

INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA. 92108

BOREHOLE/WELL LOG LEGEND

Page 1 of 2

GRAIN SIZES

U.S. Standard Series Sieve					Clear Square Sieve Openings			
200		40		10	4	3/4"	3"	12"
SILT and CLAYS	SAND			GRAVEL		COBBLES	BOULDERS	
	Fine	Medium	Coarse	Fine	Coarse			

RELATIVE DENSITY

Sand and Gravels	Blows/Foot [†]
Very Loose	0 - 4
Loose	4-10
Medium Dense	10-30
Dense	30-50
Very Dense	Over 50




CONSISTENCY

Silt and Clays	Strength [‡]	Blows/Foot [†]
Very Loose	0 - 1/4	0 - 2
Soft	1/4 - 1/2	2 - 4
Firm	1/2 - 1	2 - 4
Stiff	1 - 2	8 - 16
Very Stiff	2 - 4	16 - 32
Hard	Over 4	Over 32

[†] Number of blows of 140 pound hammer falling 30 inches to drive a 2 inch O.D. (1-3/8 inch I.D.) split Spoon (ASTM D-1586).

[‡] Unconfined compressive strength in tons/sq.ft. as determined by laboratory testing or approximated by the standard penetration test (AST D-1586), pocket penetrometer, torvane, or visual observation.

Graphic Log Symbols

-  Free Product
-  Ground Water (Static)
-  Ground Water (First Encountered)








Well Design Symbol

-  Centralizer

Abbreviations Used

- ags Above Ground Surface
- msl Mean Sea Level
- A/C Asphalt/Concrete
- Bent Bentonite
- bgs Below Ground Surface
- dia Diameter
- ' Feet
- FP Free Product
- GW Groundwater
- HC Hydrocarbon
- " Inches
- med Medium
- mod Moderate
- NR Not Recorded
- ppm Parts Per Million

Abbreviations Used

-  Asphalt
-  Concrete
-  Concrete Slurry
-  Bentonite
-  Bentonite Grout
-  Sand
-  Screened Interval

SECOR

INTERNATIONAL INCORPORATED
2655 CAMINO DEL RIO N., SUITE 302
SAN DIEGO, CA 92108

BOREHOLE/WELL LOG LEGEND

Page 2 of 2

APPENDIX F

**MONITORING WELL GAUGING LOG;
WELL PURGING/SAMPLING LOGS**

Susan Davey Property

Site Name & Facility No:

Date: 2/19/02

Project Number:

080T.048925.00 / 0010

Field Representative(s):

04926

Checked by:

[illegible]

Notes: 1 = feet above mean sea level unless noted otherwise

* = elevation adjusted by adding (.75 x product thickness) to measured water elevation

— = not measured due to the presence of liquid-phase hydrocarbons

Sheen = discontinuous, non-measurable thickness of LPH
Trace = continuous, non-measurable thickness of LPH

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: M. Siebert

Checked by: M. J. J.

Well No:

MW- 1

Date:

2/19/02

Sample Time:

1140

Sample No:

MW- 1

PURGING & SAMPLING EQUIPMENT / METHOD

WELL SPECIFICATIONS & MEASUREMENTS

Water Level Meter Type & ID: Solinst # 5

Borehole Diameter (in): 8 10 12 Vault

Purging Equipment / Method: ☐ Vac Truck ☒ Bailer
Submersible Pump ☐ Other

Casing Diameter (in): 2 4 6 8 10 12

pH Temp/Conductivity Meter Type / ID: Cole Parmer CP-1

Depth to Water (DTW₁) (ft): 9.80

Sampling Method: ☐ Teflon Bailer ☒ Disposable Bailer
Other:

Total Well Depth
(DTB) (ft): 20.00

Water Column: 10.20

Decontamination Method: ☒ Steam / High Pressure Wash
☒ 3 Stage (Alconox, Tap & DI rinse)
Other:

Floating Product:

Thickness (in):

Borehole
Volume (gal): 15.30

1.5 Borehole
Volumes (gal): 22.95

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (μ mhos)	Water Description (odor, turbidity, color)
1100	Started Purging					
1109	14.39	15	6.64	19.4	1370	No odor, Cloudy, Brown
1119	15.51	23	6.69	19.3	1389	" " "
1140	10.94	SAMPLE				

Maximum Drawdown (DTW₂) (ft) = 15.51

☒ Fast Recharging Well

Pump Rate (GPM) = 1.21

☐ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: 1140

Depth to Water at time of sampling (DTW₃): 10.94

Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
2 or <u>3</u> x 40ml VOAs		<u>HCL & ICE</u> or NONE	TPHg, BTEX, MTBE, (8015, 8260)
			DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

RECOVERY CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

Notes:

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_3)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(9.80) - (10.94)}{(9.80) - (15.51)} = \frac{-1.14}{-5.71} = 80\%$$

80% Recharge = 10.94

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: M. Siebert

Checked by: M. O'Neil

Well No: MW- 2

Date: 2/19/02

Sample Time: 1452

Sample No: MW- 2

PURGING & SAMPLING EQUIPMENT / METHOD

WELL SPECIFICATIONS & MEASUREMENTS

Water Level Meter Type & ID: Solinst # 5

Borehole Diameter (in): 8 10 12 Vault

Purging Equipment / Method: ☐ Vac Truck ☒ Bailer
☐ Submersible Pump ☐ Other

Casing Diameter (in): 2 4 6 8 10 12

pH Temp/Conductivity Meter Type / ID: Cole Parmer CP-1

Depth to Water (DTW₁) (ft): 10.92

Sampling Method: ☐ Teflon Bailer ☒ Disposable Bailer
☐ Other:

Total Well Depth (DTB) (ft): 20.10

Water Column: 9.18

Decontamination Method: ☒ Steam / High Pressure Wash
☒ 3 Stage (Alconox, Tap & DI rinse)
☐ Other:

Floating Product:

Thickness (in):

Borehole Volume (gal): 13.77

1.5 Borehole Volumes (gal): 20.66

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (µ mhos)	Water Description (odor, turbidity, color)
1205	Started Purging					
1212	DEY	14	6.93	20.2	1260	Slight Odor, Cloudy, Brown
1252	DEY	21	6.98	22.0	1298	" " "
1452	13.75	SAMPLE				

Maximum Drawdown (DTW₂) (ft) = 20.10

Pump Rate (GPM) = 0.45

☒ Fast Recharging Well
☒ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: 1452

Depth to Water at time of sampling (DTW₃): 13.75

Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
2 or <u>3</u> x 40ml VOAs		<u>HCL & ICE</u> or NONE	TPHg, BTEX, MTBE, (8015, 8260) DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

RECOVERY CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

Notes:

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_3)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(10.92) - (13.75)}{(10.92) - (20.10)} = \frac{-2.83}{-9.18} = 69\%$$

80% Recharge = 12.76

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: *M. Siebert*

Checked by: *M. O'Neil*

Well No: MW- 3

Date: 2/19/02

Sample Time: 1128

Sample No: MW- 3

PURGING & SAMPLING EQUIPMENT / METHOD

WELL SPECIFICATIONS & MEASUREMENTS

Water Level Meter Type & ID: Solinst # <i>5</i>	Borehole Diameter (in): 8 (10) 12 Vault
Purging Equipment / Method: <input type="checkbox"/> Vac Truck <input checked="" type="checkbox"/> Bailer <input type="checkbox"/> Submersible Pump <input type="checkbox"/> Other	Casing Diameter (in): 2 (4) 6 8 10 12
pH Temp/Conductivity Meter Type / ID: <i>Cole Parmer CP-1</i>	Depth to Water (DTW ₁) (ft): <i>8.70</i>
Sampling Method: <input type="checkbox"/> Teflon Bailer <input checked="" type="checkbox"/> Disposable Bailer	Total Well Depth (DTB) (ft): 17.60
Other: _____	Water Column: <i>8.90</i>
Decontamination Method: <input checked="" type="checkbox"/> Steam / High Pressure Wash	Floating Product: _____
<input checked="" type="checkbox"/> 3 Stage (Alconox, Tap & DI rinse)	Thickness (in): _____
Other: _____	Borehole Volume (gal): <i>13.35</i>
	1.5 Borehole Volumes (gal): <i>20.03</i>

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (µ mhos)	Water Description (odor, turbidity, color)
<i>1007</i>	Started Purging					
<i>1019</i>	<i>DRY</i>	<i>13</i>	<i>6.62</i>	<i>27.0</i>	<i>1206</i>	<i>No Odor, Cloudy, Brown</i>
<i>1042</i>	<i>DRY</i>	<i>20</i>	<i>6.95</i>	<i>25.2</i>	<i>1329</i>	
<i>1128</i>	<i>9.63</i>	<i>SAMPLE</i>				

Maximum Drawdown (DTW₂) (ft) = *17.60*

Pump Rate (GPM) = *0.57*

☒ Fast Recharging Well

☐ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: <i>1128</i>	Depth to Water at time of sampling (DTW ₃): <i>9.63</i>		
Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
<i>2 or (3) x 40ml VOAs</i>		HCL & ICE or NONE	TPHg, BTEX, MTBE, (8015, 8260)
			DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

RECOVERY CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

Notes:

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_3)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(8.70) - (9.63)}{(8.70) - (17.60)} = \frac{-0.93}{-8.90} = 90\%$$

80% Recharge = *10.48*

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: *M. Siegent*

Checked by: *M. off*

Well No: MW- 4

Date: 2/19/02

Sample Time: *1338*

Sample No: MW- 4

PURGING & SAMPLING EQUIPMENT / METHOD

WELL SPECIFICATIONS & MEASUREMENTS

Water Level Meter Type & ID: Solinist # *5*

Borehole Diameter (in): 8 **10** 12 Vault

Purging Equipment / Method: ☐ Vac Truck ☒ Bailer
☐ Submersible Pump ☐ Other

Casing Diameter (in): 2 **4** 6 8 10 12

pH Temp/Conductivity Meter Type / ID: *Cole Parmer CP-1*

Depth to Water (DTW₁) (ft): *9.88*

Sampling Method: ☐ Teflon Bailer ☒ Disposable Bailer
☐ Other:

Total Well Depth (DTB) (ft): 20.25

Water Column: *10.37*

Decontamination Method: ☒ Steam / High Pressure Wash
☒ 3 Stage (Alconox, Tap & DI rinse)
☐ Other:

Floating Product:

Thickness (in):

Borehole Volume (gal): *15.56*

1.5 Borehole Volumes (gal): *23.33*

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (μ mhos)	Water Description (odor, turbidity, color)
<i>1230</i>	Started Purging					
<i>1240</i>	<i>13.13</i>	<i>16</i>	<i>6.80</i>	<i>22.3</i>	<i>1192</i>	<i>No Odor, Cloudy, Brown Black</i>
<i>1246</i>	<i>12.27</i>	<i>23</i>	<i>6.81</i>	<i>22.2</i>	<i>1253</i>	<i>" " "</i>
<i>1338</i>	<i>9.88</i>	<i>SAMPLE</i>	<i>—</i>	<i>—</i>	<i>—</i>	<i>—</i>

Maximum Drawdown (DTW₂) (ft) = *13.13*

☒ Fast Recharging Well

Pump Rate (GPM) = *1.44*

☐ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: *1338* Depth to Water at time of sampling (DTW₃): *9.88*

Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
<i>2 or 3</i> x 40ml VOAs		HCL & ICE or NONE	TPHg, BTEX, MTBE, (8015, 8260) DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

RECOVERY CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_2)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(9.88) - (9.88)}{(9.88) - (13.13)} = \frac{-0.00}{-3.25} = 100\%$$

Notes:

80% Recharge = *10.53*

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: M. Siebert

Checked by: M. O'Leary

Well No: MW- 5

Date: 2/19/02

Sample Time: 1345

Sample No: MW- 5

PURGING & SAMPLING EQUIPMENT / METHOD

Water Level Meter Type & ID: Solinst # 5

Purging Equipment / Method: ☐ Vac Truck ☒ Bailer
☐ Submersible Pump ☐ Other

pH Temp/Conductivity Meter Type / ID: Cole Parmer CP-1

Sampling Method: ☐ Teflon Bailer ☒ Disposable Bailer
☐ Other:

Decontamination Method: ☒ Steam / High Pressure Wash
☒ 3 Stage (Alconox, Tap & DI rinse)
☐ Other:

WELL SPECIFICATIONS & MEASUREMENTS

Borehole Diameter (in): 8 10 12 Vault

Casing Diameter (in): 2 4 6 8 10 12

Depth to Water (DTW₁) (ft): 10.81

Total Well Depth (DTB) (ft): 19.00

Water Column: 8.19

Floating Product:

Thickness (in):

Borehole Volume (gal): 6.63

1.5 Borehole Volumes (gal): 9.95

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (μ mhos)	Water Description (odor, turbidity, color)
1310	Started Purging					
1318	15.05	7	6.74	23.0	1201	No Odor, Cloudy, Brown
1325	14.91	10	6.73	23.2	1261	" " "
1345	10.82	SAMPLE	—	—	—	—

Maximum Drawdown (DTW₂) (ft) = 15.05

Pump Rate (GPM) = 0.67

☒ Fast Recharging Well

☐ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: 1345		Depth to Water at time of sampling (DTW ₃): 10.82	
Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
2 or 3 x 40ml VOAs		HCL & ICE or NONE	TPHg, BTEX, MTBE, (8015, 8260)
			DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

Notes:

RECOVERY CALCULATIONS

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_3)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(10.81) - (10.82)}{(10.81) - (15.05)} = \frac{-0.01}{-4.24} = 100\%$$

80% Recharge =

11.66

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: *M. Siebert*

Checked by: *M. J. [Signature]*

Well No: MW- 6

Date: 2/19/02

Sample Time: 1426

Sample No: MW- 6

PURGING & SAMPLING EQUIPMENT / METHOD

WELL SPECIFICATIONS & MEASUREMENTS

Water Level Meter Type & ID: Solinist # 5

Borehole Diameter (in): 8 10 12 Vault

Purging Equipment / Method: ☐ Vac Truck ☒ Bailer
☐ Submersible Pump ☐ Other

Casing Diameter (in): 2 4 6 8 10 12

pH Temp/Conductivity Meter Type / ID: Cole Parmer CPH

Depth to Water (DTW₁) (ft): 8.66

Sampling Method: ☐ Teflon Bailer ☒ Disposable Bailer
☐ Other:

Total Well Depth (DTB) (ft): 18.50

Water Column: 9.84

Decontamination Method: ☒ Steam / High Pressure Wash
☒ 3 Stage (Alconox, Tap & DI rinse)
☐ Other:

Floating Product:

Thickness (in):

Borehole Volume (gal): 7.97

1.5 Borehole Volumes (gal): 11.96

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (μ mhos)	Water Description (odor, turbidity, color)
1400	Started Purging					
1406	9.99	8	6.88	20.0	1436	No Odor, cloudy, Brown
1412	10.31	12	6.83	21.9	1367	" " "
1426	8.66	SAMPLE				

Maximum Drawdown (DTW₂) (ft) = 10.31

☒ Fast Recharging Well

Pump Rate (GPM) = 1.00

☐ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: 1426		Depth to Water at time of sampling (DTW ₃): 8.66	
Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
2 or 3 x 40ml VOAs		HCL & ICE or NONE	TPHg, BTEX, MTBE, (8015, 8260)
			DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

RECOVERY CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

Notes:

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_2)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(8.66) - (8.66)}{(8.66) - (10.31)} = \frac{-0.00}{-1.65} = 100\%$$

80% Recharge =

8.99

SECOR

INTERNATIONAL
INCORPORATED

WELL PURGING / SAMPLING LOG

Project Name: Susan Davey Property

Project Number: 08OT.04926.00 / 0010

SECOR Rep: M. S. Sert / M. O. Iphart

Checked by: M. O. Iphart

Well No:

MW- 7

Date: 2/19/02

Sample Time: 1104

Sample No: MW- 7

PURGING & SAMPLING EQUIPMENT / METHOD

WELL SPECIFICATIONS & MEASUREMENTS

Water Level Meter Type & ID: Solinist # 5

Borehole Diameter (in): 8 10 12 Vault

Purging Equipment / Method: ☐ Vac Truck ☒ Bailer
☐ Submersible Pump ☐ Other

Casing Diameter (in): 2 4 6 8 10 12

pH Temp/Conductivity Meter Type / ID: Lde Parmer EP-1

Depth to Water (DTW₁) (ft): 10.70Sampling Method: ☐ Teflon Bailer ☒ Disposable Bailer
Other:Total Well Depth
(DTB) (ft): 20.00

Water Column: 9.30

Decontamination Method: ☒ Steam / High Pressure Wash
☒ 3 Stage (Alconox, Tap & DI rinse)
Other:

Floating Product:

Thickness (in):

Borehole
Volume (gal): 7.531.5 Borehole
Volumes (gal): 11.30

PURGING INFORMATION

Time	DTW (ft)	Water Volume Purged (gal)	pH	Temp (°C)	Elect. Cond. (μ mhos)	Water Description (odor, turbidity, color)
1000	Started Purging					
1022	DRY	8	6.73	25.2	1397	BROWN, NO ODOR, BROWN
1035	DRY	11	6.95	24.3	1382	" " " "
1104	12.56	SAMPLE				

Maximum Drawdown (DTW₂) (ft) = 20.00

Pump Rate (GPM) = 0.31

☒ Fast Recharging Well☐ Slow Recharging Well

SAMPLING INFORMATION

Time Sampled: 1104		Depth to Water at time of sampling (DTW ₃): 12.56	
Container Types & Volumes	Filtered (Y/N)	Sample Preservatives	Analytical Parameters
2 or 3 x 40ml VOAs		HCL & ICE or NONE	TPHg, BTEX, MTBE, (8015, 8260)
			DIPE, TAME, ETBE, TBA (8260b)

BOREHOLE VOLUME CALCULATIONS

RECOVERY CALCULATIONS

The calculation of one borehole volume is based on the formula in the SAM Manual.

Casing Diameter (in)	Borehole Diameter (in)	Calculated Borehole Volume (gal)
2	8	.81 (DTB-DTW ₁)
2	10	1.14 (DTB-DTW ₁)
4	10	1.50 (DTB-DTW ₁)
4	12	1.95 (DTB-DTW ₁)

Notes:

$$\% \text{ of Recovery} = 1 - \frac{(DTW_1) - (DTW_3)}{(DTW_1) - (DTW_2)} \times 100$$

$$\% \text{ of Recovery} = 1 - \frac{(10.70) - (12.56)}{(10.70) - (20.00)} = \frac{-1.86}{-9.30} = 80\%$$

80% Recharge = 12.56

APPENDIX G
WASTE DISPOSAL DOCUMENTATION

NON-HAZARDOUS WASTE MANIFEST

1. Generator's US EPA ID No.

Manifest
Document No.
20640

2. Page 1
of 1

3. Generator's Name and Mailing Address
Susan Davey Property
1279/1281 E. Main St., El Cajon, CA 92020
4. Generator's Phone (619-296-6195 Contact: Brian Demmis

5. Transporter 1 Company Name
EFR Environmental Services, Inc.

6. US EPA ID Number
C A R 0 0 0 0 1 1 2 0 5

A. Transporter's Phone 619-956-2770

7. Transporter 2 Company Name

8. US EPA ID Number

B. Transporter's Phone

9. Designated Facility Name and Site Address
Dome Rock Industries, Inc.
3125 W. Dome Rock Road
Quartzsite, AZ 85359

10. US EPA ID Number

A Z R 0 0 0 0 3 5 9 1 5

C. Facility's Phone

928-927-7688


11. Waste Shipping Name and Description

12. Containers
No. Type

13.
Total
Quantity

14.
Unit
Wt/Vol

a. Non-Hazardous Waste Liquid



002 Dm 00110

G

b. Non-Hazardous Waste Solid

002 Dm 01000

P

c.

d.

D. Additional Descriptions for Materials Listed Above
11a. Acceptance# (Purge Water)
11b. Acceptance# (Soil Cuttings)
6195PW074
6195SC05

E. Handling Codes for Wastes Listed Above

11a. 01
11b. 01

15. Special Handling Instructions and Additional Information

ALWAYS WEAR APPROPRIATE P.P.E. AND USE SAFE HANDLING METHODS
Please mail C/O Secor International, Inc.-2655 Camino Del Rio No. Ste. 302
San Diego, CA 92108-1633

16. GENERATOR'S CERTIFICATION: I certify the materials described above on this manifest are not subject to federal regulations for reporting proper disposal of Hazardous Waste.

Printed/Typed Name
Octavio Quintero (Agent)

Signature
Octavio Quintero

Month Day Year
03/20/02

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name
Octavio Quintero

Signature
Octavio Quintero

Month Day Year
03/20/02

18. Transporter 2 Acknowledgement of Receipt of Materials

Printed/Typed Name

Signature

Month Day Year
- - -

19. Discrepancy Indication Space

20. Facility Owner or Operator: Certification of receipt of waste materials covered by this manifest except as noted in Item 19.

Printed/Typed Name
JERRY R. JARRETT

Signature
Jerry R. Jarrett

Month Day Year
03/23/02

ORIGINAL - RETURN TO GENERATOR


GENERATOR

TRANSPORTER


FACILITY

APPENDIX H

**SUBSURFACE SOIL AND GROUNDWATER LABORATORY REPORTS
AND
CHAIN-OF-CUSTODY DOCUMENTATION**



2/14/02



Secor International
2655 Camino Del Rio North
San Diego, CA

Project Name: Susan Davy Property - San Diego
Project No.: 080T.04926

Attention: Mr. Peter Rubens

The following sample(s) were received and analyzed:

<u>Date Received</u>	<u>Quantity</u>	<u>Matrix</u>	<u>Date Received</u>	<u>Quantity</u>	<u>Matrix</u>
2/8/02	7	soil			

The samples were analyzed by one or more of the EPA methodologies or equivalent methods listed below.

TPH -- CA DHS "Total Petroleum Hydrocarbons"
VOCs -- EPA Method 8260

The results are included with a summary of the quality control procedures. Please note that the symbol "nd" indicates a value below the reporting limit for the particular compound in the sample.

Please feel free to call us to discuss any part of this report or to schedule future projects.


Sincerely,


Tamara Davis
Lab Director

Mobile One Laboratories is certified by the California Department of Health Services (certificate #s: 1194, 1561, 1921, 2088, 2278).

HP Labs Project # SE021102-31

148 S. Vinewood Street • Escondido, CA 92029 • Phone (760) 735-3208 • Fax (760) 735-2469
432 N. Cedros Avenue • Solana Beach, CA 92075 • Phone (858) 793-0401 • Fax (858) 793-0404
2373 208th Street Suite F-1 • Torrance, CA 90501 • Phone (310) 782-2929 • Fax (310) 782-2798




Report Summary

Matrix: soil
Units: mg/kg

Client: Secor International
Project: Susan Davy Property - San Diego

Method =	TPH
Analyte =	Gasoline C ₈ -C ₁₂
Detection Limit -	10
SAMPLE I.D.	
Date Analyzed: 02/12/02	
blank	nd
SS-1	nd
SS-2	nd
SS-3	nd
SS-4	nd
SS-5	nd
SS-6	nd
SS-7	nd

Footnotes: See Footnote Summary page.
Analyses performed by: A. Kim
SE021102-31



Client: Secor International
Project: Susan Davy Property - San Diego

Sample Name:

Analysis Date

Analysis Time

Dilution Factor:

Purge Volume(cc):

Compound

SS-1

12 Feb 2002

7:50 pm

1

SS-2

12 Feb 2002

8:11 pm

1

SS-3

12 Feb 2002

8:32 pm

1

SS-4

12 Feb 2002

8:54 pm

1

SS-5

13 Feb 2002

12:26 pm

1

SS-6

13 Feb 2002

12:50 pm

1

Matrix: soil
Units: ug/kg

E.Q.L. Amount Found Amount Found Amount Found Amount Found Amount Found Amount Found

Methyl-t-butylether (MTBE)	10	nd	nd	nd	nd	nd
Benzene	10	nd	nd	nd	nd	nd
Toluene	10	nd	nd	nd	nd	nd
Ethylbenzene	10	nd	nd	nd	nd	nd
m,p-Xylene	10	nd	nd	nd	nd	nd
o-Xylene	10	nd	nd	nd	nd	nd

Surrogates Spiked QC Limits(% Rec.)


DBFM	50 ng	65-135	104
1,2-DCA-d4	50 ng	52-149	128
Toluene - d8	50 ng	65-135	110
1,4-BFB	50 ng	65-135	105

Percent Recovery

106	104	99	103
133	130	115	122
110	108	110	111
108	108	104	106

Analyses performed by: A. Kim

SE021102-31



Client: Secor International
Project: Susan Davy Property - San Diego

Matrix: soil
Units: ug/kg

Sample Name: SS-7
Analysis Date: 13 Feb 2002
Analysis Time: 6:14 pm
Dilution Factor: 1
Purge Volume(cc): 1

blank
12 Feb 2002
10:37 am
1

blank
13 Feb 2002
11:56 am
1

Amount Found Amount Found

nd nd
nd nd
nd nd
nd nd
nd nd
nd nd

Percent Recovery

102 100
118 117
110 111
106 105

E.Q.L. Amount Found


Methyl-t-butylether (MTBE) 10 nd
Benzene 10 nd
Toluene 10 nd
Ethylbenzene 10 nd
m,p-Xylene 10 nd
o-Xylene 10 nd

Surrogates Spiked QC Limits(% Rec.)

DBFM 50 ng 65-135 96
1,2-DCA-d4 50 ng 52-149 112
Toluene - d8 50 ng 65-135 109
1,4-BFB 50 ng 65-135 102

Analyses performed by: A. Kim

SE021102-31



QC Summary

Client: Secor International
Project: Susan Davy Property - San Diego
Matrix: soil

Method 8260	1,1-DCE	Benzene	TCE	Toluene	Cl-Benz
	(65-135)	(65-135)	(65-135)	(64-135)	(65-135)
Recovery % QC Limits	<30	<30	<30	<30	<30
RPD - % QC Limits	<30	<30	<30	<30	<30
Date Analyzed: 2/12/02					
Spike Level (ug/kg)	50.0	50.0	50.0	50.0	50.0
Sample Amount	0.0	0.0	0.0	2.2	0.0
MS Amount Found	51.2	53.0	52.3	55.4	44.4
MSD Amount Found	53.4	55.4	55.1	56.5	47.7
MS Recovery	102.4	106.0	104.5	106.4	88.8
MSD Recovery	106.8	110.8	110.2	108.6	95.4
RPD - %	4.2	4.4	5.3	2.0	7.2
Date Analyzed: 2/13/02					
Spike Level (ug/kg)	50.0	50.0	50.0	50.0	50.0
Sample Amount	0.0	0.3	0.0	3.8	0.0
MS Amount Found	51.5	52.5	52.0	56.3	45.7
MSD Amount Found	55.3	57.8	58.1	60.9	50.9
MS Recovery	103.0	104.4	104.0	105.0	91.3
MSD Recovery	110.6	114.9	116.2	114.2	101.8
RPD - %	7.0	9.6	11.0	8.4	10.9

Calibration verification was within acceptable limits.

SE021102-31



Matrix: soil
Units: ug/kg


Client: Secor International
Project: Susan Davy Property - San Diego

Sample Name: ccv
Analysis Date: 12 Feb 2002
Analysis Time: 9:47 am
Dilution Factor: 1

CCC (-20 to +20%)
Pass

EPA 8260 (-20 to +20%)
Pass

Compound	Amount Found	Percent Diff	CCC (-20 to +20%) Pass	EPA 8260 (-20 to +20%) Pass
Dichlorodifluoromethane	49	-3		yes
Chloromethane	39	-21		no
Vinyl Chloride	46	-9	yes	yes
Bromomethane	54	8		yes
Chloroethane	44	-12		yes
Trichlorofluoromethane	57	13		yes
1,1-Dichloroethene	51	2	yes	yes
Methylene Chloride	49	-3		yes
Methyl-t-butylether	47	-6		yes
trans-1,2-Dichloroethene	51	2		yes
1,1-Dichloroethane	45	-11		yes
2,2-Dichloropropane	57	15		yes
cis-1,2-Dichloroethene	49	-2		yes
Chloroform	56	12	yes	yes
Bromochloromethane	42	-16		yes
1,1,1-Trichloroethane	55	11		yes
1,1-Dichloropropene	53	6		yes
Carbon Tetrachloride	50	0		yes
1,2-Dichloroethane	53	5		yes
Benzene	50	1		yes
Trichloroethene	50	1		yes
1,2-Dichloropropane	40	-20	no	no
Bromodichloromethane	52	3		yes
Dibromomethane	44	-12		yes
cis-1,3-Dichloropropene	48	-5		yes
Toluene	52	4	yes	yes
trans-1,3-Dichloropropene	47	-5		yes
1,1,2-Trichloroethane	44	-12		yes
1,2-Dibromoethane	40	-19		yes
1,3-Dichloropropane	41	-17		yes



Client: Secor International
Project: Susan Davy Property - San Diego

Matrix: soil
Units: ug/kg


EPA 8260
(-20 to +20%)

Sample Name:		ccv	Pass
Compound	Amount Found	Percent Diff	
Tetrachloroethene	40	-20	no
Dibromochloromethane	36	-27	no
Chlorobenzene	43	-15	yes
Ethylbenzene	44	-12	yes
1,1,1,2-Tetrachloroethane	42	-16	yes
m,p-Xylene	87	-13	yes
o-Xylene	43	-14	yes
Styrene	42	-16	yes
Bromoform	41	-19	yes
Isopropylbenzene	50	0	yes
1,1,2,2-Tetrachloroethane	41	-18	yes
1,2,3-Trichloropropane	46	-9	yes
n-propylbenzene	54	9	yes
Bromobenzene	48	-4	yes
1,3,5-Trimethylbenzene	52	3	yes
2-Chlorotoluene	55	10	yes
4-Chlorotoluene	55	9	yes
tert-Butylbenzene	48	-4	yes
1,2,4-Trimethylbenzene	50	0	yes
sec-Butylbenzene	48	-3	yes
p-Isopropyltoluene	48	-5	yes
1,3-Dichlorobenzene	45	-9	yes
1,4-Dichlorobenzene	45	-10	yes
n-Butylbenzene	53	6	yes
1,2-Dichlorobenzene	43	-14	yes
1,2-Dibromo-3-chloropropane	37	-26	no
1,2,4-Trichlorobenzene	45	-9	yes
Hexachlorobutadiene	49	-1	yes
Naphthalene	36	-27	no
1,2,3-Trichlorobenzene	43	-14	yes
Surrogates	Spiked	QC Limits(% Rec.)	
DBFM	50 ng	80-120	93
1,2-DCA-d4	50 ng	65-135	110
Toluene - d8	50 ng	80-120	104
1,4-BFB	50 ng	65-135	97


SUMMATION

All compounds PASS the average % Diff. Criteria
54 compounds PASS the 20% criteria

CALIBRATION VERIFIED

Matrix: soil
Units: ug/kgClient: Secor International
Project: Susan Davy Property - San DiegoSample Name: ccv
Analysis Date: 13 Feb 2002
Analysis Time: 8:52 am
Dilution Factor: 1CCC
(-20 to +20%)
PassEPA 8260
(-20 to +20%)
Pass

Compound	Amount Found	Percent Diff	CCC (-20 to +20%) Pass	EPA 8260 (-20 to +20%) Pass
Dichlorodifluoromethane	48	-3		yes
Chloromethane	39	-22		no
Vinyl Chloride	44	-13	yes	yes
Bromomethane	54	7		yes
Chloroethane	46	-8		yes
Trichlorofluoromethane	58	15		yes
1,1-Dichloroethene	53	6	yes	yes
Methylene Chloride	50	1		yes
Methyl-t-butylether	64	28		no
trans-1,2-Dichloroethene	54	8		yes
1,1-Dichloroethane	47	-6		yes
2,2-Dichloropropane	58	16		yes
cis-1,2-Dichloroethene	51	1		yes
Chloroform	57	15	yes	yes
Bromochloromethane	42	-16		yes
1,1,1-Trichloroethane	58	15		yes
1,1-Dichloropropene	56	12		yes
Carbon Tetrachloride	53	6		yes
1,2-Dichloroethane	53	5		yes
Benzene	53	7		yes
Trichloroethene	53	7		yes
1,2-Dichloropropane	42	-16	yes	yes
Bromodichloromethane	53	5		yes
Dibromomethane	45	-11		yes
cis-1,3-Dichloropropene	49	-1		yes
Toluene	60	20	no	no
trans-1,3-Dichloropropene	49	-3		yes
1,1,2-Trichloroethane	44	-12		yes
1,2-Dibromoethane	40	-21		no
1,3-Dichloropropane	41	-18		yes



Calibration verification

EPA Method 8260B


Client: Secor International
Project: Susan Davy Property - San Diego

Matrix: soil
Units: ug/kg

EPA 8260
(-20 to +20%)

Sample Name:		ccv	Percent Diff		Pass
Compound	Amount Found				
Tetrachloroethene	42	-16	yes		
Dibromochloromethane	36	-29	no		
Chlorobenzene	43	-15	yes		
Ethylbenzene	46	-7	yes		
1,1,1,2-Tetrachloroethane	42	-15	yes		
m,p-Xylene	94	-6	yes		
o-Xylene	45	-10	yes		
Styrene	43	-14	yes		
Bromoform	41	-18	yes		
Isopropylbenzene	54	9	yes		
1,1,2,2-Tetrachloroethane	42	-17	yes		
1,2,3-Trichloropropane	45	-10	yes		
n-propylbenzene	60	21	no		
Bromobenzene	51	2	yes		
1,3,5-Trimethylbenzene	56	12	yes		
2-Chlorotoluene	59	18	yes		
4-Chlorotoluene	58	16	yes		
tert-Butylbenzene	52	4	yes		
1,2,4-Trimethylbenzene	59	17	yes		
sec-Butylbenzene	52	5	yes		
p-Isopropyltoluene	52	5	yes		
1,3-Dichlorobenzene	48	-4	yes		
1,4-Dichlorobenzene	47	-6	yes		
n-Butylbenzene	59	18	yes		
1,2-Dichlorobenzene	43	-15	yes		
1,2-Dibromo-3-chloropropane	40	-20	yes		
1,2,4-Trichlorobenzene	49	-2	yes		
Hexachlorobutadiene	55	11	yes		
Naphthalene	40	-20	yes		
1,2,3-Trichlorobenzene	45	-10	yes		
Surrogates	Spiked	QC Limits(% Rec.)	SUMMATION		
DBFM	50 ng	80-120	92	All compounds	PASS
1,2-DCA-d4	50 ng	65-135	107	the average % Diff. Criteria	
Toluene - d8	50 ng	80-120	105	54 compounds	PASS
1,4-BFB	50 ng	65-135	98	the 20% criteria	
					CALCULATION VERIFIED

CALIBRATION VERIFIED



Footnote Summary

<u>Footnote</u>	<u>Definition</u>
E.Q.L. nd J	Estimated Quantitation Limit Not detected above the E.Q.L. or detection limit. The concentration reported is between the Method Detection Limit and the E.Q.L.
D	Concentration reported from a secondary dilution; E.Q.L.s adjusted accordingly.
B E	Analyte found in the associated blank. Analyte amount exceeds calibration range. Amount quantitated by extrapolation.
***	MS/MSD, LCS/LCSD recovery is outside QC range; no corrective action taken.
M S	Surrogate recovery outside QC range due to matrix interference. Because of necessary sample dilution, value was outside QC limits.
& #	Gasoline range organics not identified as gasoline. Diesel range organics not identified as diesel.
**	This compound has been screened by EPA method 8020. Any positive results should be confirmed by a second analysis.

RELINQUISHED BY: (Signature)	DATE/TIME	RECEIVED BY: (Signature)	DATE/TIME	SAMPLE RECEIPT TOTAL NUMBER OF CONTAINERS <u>7</u> CHAIN OF CUSTODY SEALS Y/N/A SEALS INTACT? Y/N/A RECEIVED GOOD COND./COLD NOTES:
<i>Brian M. Lane</i>	<u>2/8/02</u>	<i>Latasha A. Adams</i>	<u>2/8/02 1:40p</u>	
RELINQUISHED BY: (Signature)	DATE/TIME	RECEIVED BY: (Signature)	DATE/TIME	
SAMPLE DISPOSAL INSTRUCTIONS <input type="checkbox"/> REQ. DISPOSAL @ 30m/yr. <input type="checkbox"/> Return <input type="checkbox"/> Pickup				

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-1
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 08OT.04926.0007
Collected by: Brian M. Demme

Sample Description:
SB-4/5'
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	ND
Toluene	0.005	ND
Ethylbenzene	0.005	ND
Xylenes	0.005	ND
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		99
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.


Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-1.xls
DZ/sks/pv/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-2
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 080T.04926.0007
Collected by: Brian M. Demme

Sample Description:
SB-4/10'
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.1	ND
Toluene	0.1	ND
Ethylbenzene	0.1	0.4
Xylenes	0.1	1.2
Methyl-t-Butyl Ether (MTBE)	0.1	ND
Percent Surrogate Recovery		100
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	10.	80.
BTX as a Percent of Fuel		2

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-2.xls
DZ/sks/pv/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-3
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 080T.04926.0007
Collected by: Brian M. Demme

Sample Description: SB-4/12'
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.5	0.9
Toluene	0.5	21.
Ethylbenzene	0.5	20.
Xylenes	0.5	190.
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		102
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	50.	1400.
BTX as a Percent of Fuel		15

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

VS70312
MSD #7
26840-3.xls
DZ/sks/pv/jh

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-4
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 08OT.04926.0007
Collected by: Brian M. Demme

Sample Description: SB-5/5'
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	ND
Toluene	0.005	ND
Ethylbenzene	0.005	ND
Xylenes	0.005	ND
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		96
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-4.xls
DZ/sks/pv/jh

Submitted by,
ZymaX envirotechnology, inc.


Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-5
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 080T.04926.0007
Collected by: Brian M. Demme

Sample Description: SB-5/10'
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.5	1.5
Toluene	0.5	18.
Ethylbenzene	0.5	11.
Xylenes	0.5	69.
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		100
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	50.	960.
BTX as a Percent of Fuel		9

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-5.xls
DZ/sks/pv/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-6
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 080T.04926.0007
Collected by: Brian M. Demme

Sample Description:
SB-5/12'
Analyzed: 03/13/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.5	3.9
Toluene	0.5	44.
Ethylbenzene	0.5	22.
Xylenes	0.5	150.
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		107
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	50.	1800.
BTX as a Percent of Fuel		11

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-6.xls
DZ/sks/pv/ccs/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-7
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 080T.04926.0007
Collected by: Brian M. Demme

Sample Description: SB-6/5'
Analyzed: 03/13/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	ND
Toluene	0.005	ND
Ethylbenzene	0.005	ND
Xylenes	0.005	0.015
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		99
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-7.xls
DZ/sks/pv/ccc/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-8
Collected: 03/05/02
Received: 03/06/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 08OT.04926.0007
Collected by: Brian M. Demme

Sample Description:
SB-6/10'
Analyzed: 03/13/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	0.015
Toluene	0.005	0.040
Ethylbenzene	0.005	0.007
Xylenes	0.005	0.028
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		102
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70313
MSD #7
26840-8.xls
DZ/sks/pv/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Peter Rubens
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108

Lab Number: 26840-9
Collected: 3/5/02
Received: 3/6/02
Matrix: Soil

Project: Susan Davey Property
El Cajon, Ca
Project Number: 080T.04926.0007
Collected by: Brian M. Demme

Sample Description: SB-6/12'
Analyzed: 3/13/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	ND
Toluene	0.005	ND
Ethylbenzene	0.005	ND
Xylenes	0.005	ND
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		99
TOTAL PETROLEUM HYDROCARBONS		
Total Petroleum Hydrocarbons	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: MTBE not included in TPH result.

VS70312
MSD #7
26840-9.xls
DZ/sks/pv/ccc/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: BLK VS70312
Collected:
Received:
Matrix: Soil

Project:
Project Number:
Collected by:

Sample Description: Instrument Blank
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	ND
Toluene	0.005	ND
Ethylbenzene	0.005	ND
Xylenes	0.005	ND
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		99
TOTAL PETROLEUM HYDROCARBONS		
Gasoline	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

VS70312
MSD #7
VS70312c.xls
DZ/sks/pv

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: BLK VS70313
Collected:
Received:
Matrix: Soil

Project:
Project Number:
Collected by:

Sample Description:
Instrument Blank
Analyzed: 03/13/02
Method: See Below

CONSTITUENT	PQL* mg/kg	RESULT** mg/kg
Benzene	0.005	ND
Toluene	0.005	ND
Ethylbenzene	0.005	ND
Xylenes	0.005	ND
Methyl-t-Butyl Ether (MTBE)	0.005	ND
Percent Surrogate Recovery		96

TOTAL PETROLEUM HYDROCARBONS

Gasoline	0.5	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

VS70313
MSD #7
VS70313b.xls
DZ/sks/ccc

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QS VS70312
Collected:
Received:
Matrix: Soil

Project:

Project Number:
Collected by:

Sample Description:

Quality Assurance Spike
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	Amount Spiked mg/kg	Amount Recovered mg/kg	Percent Recovery
Benzene	0.012	0.011	92
Toluene	0.162	0.157	97
Ethylbenzene	0.048	0.041	85
Xylenes	0.251	0.221	88
Methyl t-Butyl Ether (MTBE)	0.145	0.152	105
Percent Surrogate Recovery			102

TOTAL PETROLEUM HYDROCARBONS

Gasoline	2.50	2.71	108
BTX as a Percent of Fuel	17	14	

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

Note: Analyzed by EPA 8260 and GC/MS Combination.

VS70312
MSD #7
VS70312q.xls
DZ/sks/jh

Submitted by,
ZymaX envirotechnology, inc.


Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QSD VS70312
Collected:
Received:
Matrix: Soil

Project:

Project Number:
Collected by:

Sample Description:
Quality Assurance Spike Duplicate
Analyzed: 03/12/02
Method: See Below

CONSTITUENT	Amount Spiked mg/kg	Amount Recovered mg/kg	Percent Recovery	Relative Percent Difference*
Benzene	0.012	0.011	92	0
Toluene	0.162	0.159	98	1
Ethylbenzene	0.048	0.042	88	2
Xylenes	0.251	0.223	89	1
Methyl t-Butyl Ether (MTBE)	0.145	0.156	108	3
Percent Surrogate Recovery			102	
TOTAL PETROLEUM HYDROCARBONS				
Gasoline	2.50	2.63	105	3
BTX as a Percent of Fuel	17	15		

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*Relative Percent Difference of the spike and spike duplicate

Note: Analyzed by EPA 8260 and GC/MS Combination.

VS70312
MSD #7
VS70312q.xls
DZ/sks/jh

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

SECOR Chain-of Custody Record

☐ Additional documents are attached, and are a part of this Record.

Field Office: SECOR INTERNATIONAL INCAddress: 2655 CAMINO DEL RIO NORTESAN DIEGO, CAJob Name: SUSAN DAVIS PROPERTYLocation: 1279/1281 EAST MAIN STEZ CAYON - CAProject # 080104926 Task # 0007Project Manager: Peter RubensLaboratory: LymaxTurnaround Time: STANDARDSampler's Name: Brian M DemmeSampler's Signature: Brian M Demme

Analysis Request

Sample ID	Date	Time	Matrix	TPH (BTEX)/TPH-G 8015 (modified)/8020	TPH (TPH-D) 8015 (modified)	TPH 418.1/MTPH 418.1	Aromatic Volatiles 602/8020	Volatile Organics 624/8240 (GC/MS)	Halogenated Volatiles 601/8010	Semi-volatile Organics 625/8270 (GC/MS)	Pesticides/PCBs 608/8080	Total Lead 7421	Priority Pollutant Metals (13)	TCLP Metals 8015/8020	Comments/ Instructions	Number of Containers
SB-4/5'	3/5	0830	Soil												Strong HC odor	26840-1
SB-4/10'		0900													Strong HC odor	-2
SB-4/12'		0915													Strong HC odor	-3
SB-5/5'		1024														-4
SB-5/10'		1040													Strong HC odor	-5
SB-5/12'		1046													Strong HC odor	-6
SB-6/5'		1207														-7
SB-6/10'		1209														-8
SB-6/12'		1221														-9

Special Instructions/Comments:
* POCs will be by 8200 per B Demme 3/6/02

Relinquished by: Brian M Demme
 Sign Brian M Demme
 Print Brian M Demme
 Company SECOR
 Time 13:35 Date 3/06/02

Received by: Brian M Demme
 Sign Brian M Demme
 Print Brian M Demme
 Company SECOR
 Time 13:35 Date 3/6/02

Sample Receipt
 Total no. of containers: 9
 Chain of custody seals:
 Rec'd in good condition/cold:
 Conforms to record:

Relinquished by: _____
 Sign _____
 Print _____
 Company _____
 Time _____ Date _____

Received by: _____
 Sign _____
 Print _____
 Company _____
 Time _____ Date _____

Client: SECOR INC
 Client Contact: Brian Demme
 Client Phone: 619 296 6195

Client: Brian Demme
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108-1633

Lab Number: 26673-1
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description:
MW-1
Analyzed: 02/24/02
Method: See Below

CONSTITUENT	PQL * ug/L	RESULT ** ug/L
Benzene	0.5	39.
Toluene	0.5	0.6
Ethylbenzene	0.5	69.
Xylenes	0.5	0.9
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	10.
Diisopropyl Ether (DIPE)	0.5	46.
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	78.
Percent Surrogate Recovery		101

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	50.	700.
BTX as a Percent of Fuel		6

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

VA70223
MSD #7
26673-1.xls
DZ/jgt/pv/cc

Client: Brian Demme
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108-1633

Lab Number: 26673-2
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description:
MW-2
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	20.	640.
Toluene	20.	83.
Ethylbenzene	20.	270.
Xylenes	20.	830.
t-Amyl Methyl Ether (TAME)	20.	ND
t-Butyl Alcohol (TBA)	200.	ND
Diisopropyl Ether (DIPE)	20.	680.
Ethyl-t-Butyl Ether (ETBE)	20.	ND
Methyl-t-Butyl Ether (MTBE)	20.	ND
Percent Surrogate Recovery		108

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	2000.	6300.
BTX as a Percent of Fuel		25

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

VA110226
MSD #11
26673-2.xls
DZ/jgt/pv/lz

Client: Brian Demme
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108-1633

Lab Number: 26673-3
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description: MW-3
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		105

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

VA110226
MSD #11
26673-3.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client: Brian Demme
 SECOR International Inc.
 2655 Camino Del Rio N., Ste. 302
 San Diego, CA 92108-1633

Lab Number: 26673-4
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description: MW-4
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	59.
Toluene	0.5	11.
Ethylbenzene	0.5	19.
Xylenes	0.5	54.
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	0.9
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	0.7
Percent Surrogate Recovery		102

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	50.	480.
BTX as a Percent of Fuel		26

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.


Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

Submitted by,
 ZymaX envirotechnology, inc.



Dwain Zsadanyi
 Project Manager

VA110226
 MSD #11
 26673-4.xls
 DZ/jgt/pv/lz

Client: Brian Demme
 SECOR International Inc.
 2655 Camino Del Rio N., Ste. 302
 San Diego, CA 92108-1633

Lab Number: 26673-5
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description: MW-5
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		104

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.


Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

VA110225
 MSD #11
 26673-5.xls
 DZ/jgt/pv/lz

Submitted by,
 ZymaX envirotechnology, inc.



Dwain Zsadanyi
 Project Manager

Client: Brian Demme
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108-1633

Lab Number: 26673-6
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description:
MW-6
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		104

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.


Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

VA110225
MSD #11
26673-6.xls
DZ/jgt/pv/lz

Client: Brian Demme
SECOR International Inc.
2655 Camino Del Rio N., Ste. 302
San Diego, CA 92108-1633

Lab Number: 26673-7
Collected: 02/19/02
Received: 02/20/02
Matrix: Aqueous

Project: Sosan Davey Property
Project Number: 080T.04926.00.0010
Collected by: Marcus Siefert

Sample Description:
MW-7
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		105

TOTAL PETROLEUM HYDROCARBONS

Total Petroleum Hydrocarbons	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Note: Analytical range is C4-C12.

Note: TPH quantitated against gasoline.

Note: Oxygenates not included in TPH result.

VA110225
MSD #11
26673-7.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: BLK VA70223
Collected:
Received:
Matrix: Aqueous

Project:

Project Number:
Collected by:

Sample Description:
Instrument Blank
Analyzed: 02/23/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		95

TOTAL PETROLEUM HYDROCARBONS

Gasoline	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

VA70223
MSD #7
VA70223b.xls
DZ/jgt/pv/cc

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QS VA70223
Collected:
Received:
Matrix: Aqueous

Project:
Project Number:
Collected by:


Sample Description:
Quality Assurance Spike
Analyzed: 02/23/02
Method: See Below

CONSTITUENT	Amount Spiked ug/L	Amount Recovered ug/L	Percent Recovery
Benzene	2.2	2.1	95
Toluene	26.5	25.7	97
Ethylbenzene	7.1	6.7	94
Xylenes	37.1	35.0	94
Methyl t-Butyl Ether (MTBE)	24.5	22.7	93
Percent Surrogate Recovery			101
TOTAL PETROLEUM HYDROCARBONS			
Gasoline	500.	517.	103
BTX as a Percent of Fuel	13	12	

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

Note: Analyzed by EPA 8260 and GC/MS Combination.

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

VA70223
MSD #7
VA70223q.xls
DZ/jgt/pv/cc



QUALITY ASSURANCE REPORT
SPIKE DUPLICATE RESULTS

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QSD VA70223
Collected:
Received:
Matrix: Aqueous

Project:
Project Number:
Collected by:

Sample Description:
Quality Assurance Spike Duplicate
Analyzed: 02/23/02
Method: See Below

CONSTITUENT	Amount Spiked ug/L	Amount Recovered ug/L	Percent Recovery	Relative Percent Difference*
Benzene	2.2	2.1	95	0
Toluene	26.5	25.9	98	1
Ethylbenzene	7.1	7.3	103	9
Xylenes	37.1	37.5	101	7
Methyl t-Butyl Ether (MTBE)	24.5	19.8	81	14
Percent Surrogate Recovery			100	

TOTAL PETROLEUM HYDROCARBONS

Gasoline	500.	474.	95	9
BTX as a Percent of Fuel	13	14		

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*Relative Percent Difference of the spike and spike duplicate

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA70223
MSD #7
VA70223q.xls
DZ/jgt/pv/cc

Submitted by,
ZymaX envirotechnology, inc.

Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: BLK VA110225
Collected:
Received:
Matrix: Aqueous

Project:
Project Number:
Collected by:

Sample Description: Instrument Blank
Analyzed: 02/25/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		105

TOTAL PETROLEUM HYDROCARBONS

Gasoline	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA110225
MSD #11
A110225b.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401**Lab Number:**

QS VA110225

Collected:**Received:****Matrix:**

Aqueous

Project:**Project Number:****Collected by:****Sample Description:**

Quality Assurance Spike

Analyzed:

02/25/02

Method:

See Below

CONSTITUENT	Amount Spiked ug/L	Amount Recovered ug/L	Percent Recovery
Benzene	3.0	2.6	87
Toluene	33.8	34.2	101
Ethylbenzene	9.0	8.9	99
Xylenes	46.7	48.7	104
Methyl t-Butyl Ether (MTBE)	34.7	40.0	115
Percent Surrogate Recovery			105

TOTAL PETROLEUM HYDROCARBONS

Gasoline	500.	545.	109
BTX as a Percent of Fuel	17	16	

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA110225
MSD #11
A110225q.xls
DZ/jgt/pv/lzSubmitted by,
ZymaX envirotechnology, inc.Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QSD VA110225
Collected:
Received:
Matrix: Aqueous

Project:
Project Number:
Collected by:

Sample Description:
Quality Assurance Spike Duplicate
Analyzed: 2/25/02
Method: See Below

CONSTITUENT	Amount Spiked ug/L	Amount Recovered ug/L	Percent Recovery	Relative Percent Difference*
Benzene	3.0	2.8	93	7
Toluene	33.8	35.6	105	4
Ethylbenzene	9.0	9.4	104	5
Xylenes	46.7	50.6	108	4
Methyl t-Butyl Ether (MTBE)	34.7	40.6	117	1
Percent Surrogate Recovery			106	

TOTAL PETROLEUM HYDROCARBONS

Gasoline	500.	570.	114	4
BTX as a Percent of Fuel	17	16		

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*Relative Percent Difference of the spike and spike duplicate

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA110225
MSD #11
A110225q.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: BLK VA110226
Collected:
Received:
Matrix: Aqueous

Project:
Project Number:
Collected by:

Sample Description: Instrument Blank
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	PQL* ug/L	RESULT** ug/L
Benzene	0.5	ND
Toluene	0.5	ND
Ethylbenzene	0.5	ND
Xylenes	0.5	ND
t-Amyl Methyl Ether (TAME)	0.5	ND
t-Butyl Alcohol (TBA)	5.0	ND
Diisopropyl Ether (DIPE)	0.5	ND
Ethyl-t-Butyl Ether (ETBE)	0.5	ND
Methyl-t-Butyl Ether (MTBE)	0.5	ND
Percent Surrogate Recovery		105

TOTAL PETROLEUM HYDROCARBONS

Gasoline	50.	ND
BTX as a Percent of Fuel		N/A

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*PQL - Practical Quantitation Limit

**Results listed as ND would have been reported if present at or above the listed PQL.

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA110226
MSD #11
A110226b.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QS VA110226
Collected:
Received:
Matrix: Aqueous

Project:

Project Number:
Collected by:

Sample Description: Quality Assurance Spike
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	Amount Spiked ug/L	Amount Recovered ug/L	Percent Recovery
Benzene	3.0	2.6	87
Toluene	33.8	30.9	91
Ethylbenzene	9.0	8.6	96
Xylenes	46.7	45.3	97
Methyl t-Butyl Ether (MTBE)	34.7	36.5	105
Percent Surrogate Recovery			99

TOTAL PETROLEUM HYDROCARBONS

Gasoline	500.	515.	103
BTX as a Percent of Fuel	17	15	

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA110226
MSD #11
A110226q.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.



Dwain Zsadanyi
Project Manager



QUALITY ASSURANCE REPORT
SPIKE DUPLICATE RESULTS

Client:
ZymaX envirotechnology, inc.
71 Zaca Lane, Suite 110
San Luis Obispo, CA 93401

Lab Number: QSD VA110226
Collected:
Received:
Matrix: Aqueous

Project:
Project Number:
Collected by:

Sample Description:
Quality Assurance Spike Duplicate
Analyzed: 02/26/02
Method: See Below

CONSTITUENT	Amount Spiked ug/L	Amount Recovered ug/L	Percent Recovery	Relative Percent Difference*
Benzene	3.0	2.6	87	0
Toluene	33.8	33.3	99	7
Ethylbenzene	9.0	9.1	101	6
Xylenes	46.7	48.3	103	6
Methyl t-Butyl Ether (MTBE)	34.7	37.8	109	3
Percent Surrogate Recovery			100	

TOTAL PETROLEUM HYDROCARBONS

Gasoline	500.	545.	109	6
BTX as a Percent of Fuel	17	15		

ZymaX envirotechnology, inc. is certified by CA Department of Health Services: Laboratory #1717

*Relative Percent Difference of the spike and spike duplicate

Note: Analyzed by EPA 8260 and GC/MS Combination.

VA110226
MSD #11
A110226q.xls
DZ/jgt/pv/lz

Submitted by,
ZymaX envirotechnology, inc.

Dwain Zsadanyi
Project Manager

Chain-of Custody Number:

SECOR Chain-of Custody Record

Field Office: San Diego
 Address: 2655 Camino Del Rio N # 302
San Diego, CA 92108

☐ Additional documents are attached, and are a part of this Record.
 Job Name: Sosa Davey Property
 Location: 1279#1281 E. Main St.
El Cajon, CA

Project # 080T.04926.00 Task # 0010
 Project Manager Brian Demme
 Laboratory SYMAX
 Turnaround Time Normal

Sampler's Name Marwus Siedert
 Sampler's Signature [Signature]

Sample ID	Date	Time	Matrix
MW-1	2/19/02	1140	H ₂ O
MW-2		1452	
MW-3		1128	
MW-4		1338	
MW-5		1345	
MW-6		1426	
MW-7		1104	

Analysis Request	HCID	TPH-G/BTEX/TPH-G 8015 (modified)/8020	TPH-D/TPH-D 8015 (modified)	TPH 418.1/WTPH 418.1	Aromatic Volatiles 602/8020	Volatile Organics 624/8240 (GC/MS)	Halogenated Volatiles 601/8010	Semi-volatile Organics 625/8270 (GC/MS)	Pesticides/PCBs 608/8080	Total Lead 7421	Priority Pollutant Metals (13)	TCLP Metals	TPH-G, BTEX, MTSE *K8260	DTE, THME, ETE, TBA, *K8260	Comments/ Instructions	Number of Containers
													X	X	20073-1	14/24
															-2	
															-3	
															-4	
															-5	
															-6	
															-7	

Special Instructions/Comments:
Please Fax Results

Relinquished by:	Received by:
Sign <u>[Signature]</u> Print <u>Marwus Siedert</u> Company <u>SECOR</u> Time <u>2:35 PM</u> Date <u>2/19/02</u>	Sign <u>[Signature]</u> Print <u>JIM WHITE</u> Company <u>SYMAX</u> Time <u>2:35 PM</u> Date <u>2/19/02</u>
Relinquished by: Sign _____ Print _____ Company _____ Time _____ Date _____	Received by: Sign _____ Print _____ Company _____ Time _____ Date _____

Sample Receipt
Total no. of containers: <u>21</u>
Chain of custody seals: _____
Rec'd in good condition/cold: _____
Conforms to record: _____
Client: _____
Client Contact: _____
Client Phone: _____